

TREE REPLACEMENT SCHEDULE

LOCATION	TREE, ULMUS CARPINIFOLIA (ACCOLADE ELM), 2" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, ACER X FREEMANII (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, (EACH)	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED (EACH)	TREE QUERCUS MACROCARPA (BUR OAK), 2" CALIPER BALLED AND BURLAPPED (EACH)	EVERGREEN PINUS STROBUS (EASTERN WHITE PINE), 5' HEIGHT, BALLED AND BURLAPPED (EACH)
45+50 50.0 LT	1						
51+50 50.0 LT		1					
52+75 50.0 LT						1	
53+00 50.0 LT		1					
53+05 50.0 LT						1	
53+25 50.0 LT			1				
53+40 50.0 LT		1					
53+50 50.0 LT		1					
55+00 45.0 LT							1
55+50 45.0 LT			1				
56+00 45.0 LT		1					
56+50 45.0 LT		1					
57+00 40.0 RT	1						
57+50 40.0 RT							1
58+50 40.0 LT							1
62+50 45.0 LT							1
63+50 40.0 RT				1			
66+50 90.0 LT			1				
69+50 45.0 LT	1						
69+60 45.0 LT	1						
69+75 45.0 LT				1			
70+50 45.0 LT		1					
71+00 45.0 LT					1		
71+25 45.0 LT						1	
71+50 45.0 LT	1						
71+75 45.0 LT	1						
72+00 45.0 LT		1					
72+50 45.0 LT			1				
75+50 40.0 LT							1
76+25 40.0 LT				1			
76+50 40.0 LT				1			
78+25 42.0 RT					1		
78+75 42.0 RT						1	
79+00 42.0 RT					1		
79+50 42.0 RT						1	
85+75 45.0 RT							1
TOTAL	6	8	4	4	4	4	6

NOTE: CONTRACTOR TO CONTACT VILLAGE OF OSWEGO PUBLIC WORKS AT 630-554-3242 PRIOR TO ORDERING TREES. ALSO, FINAL LOCATION TO BE DETERMINED BY VILLAGE OF OSWEGO PUBLIC WORKS PRIOR TO PLANTING.

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6 TO 15 UNITS) (UNITS)	TREE REMOVAL (OVER 15 UNITS) (UNITS)
45+97.23 38.9 LT	6	
50+12.40 25.4 LT	8	
52+75.21 45.6 LT	15	
53+01.72 38.8 LT	15	
53+20.54 43.4 LT	8	
53+32.26 39.4 LT	8	
53+44.40 41.0 LT	8	
53+56.28 48.5 LT	5	
54+47.69 52.7 LT	15	
55+31.39 44.3 LT	15	
55+59.33 44.9 LT	15	
56+60.83 53.7 LT	15	
56+83.37 59.77 RT	15	
57+74.54 40.4 RT		23
58+51.42 37.5 LT	15	
62+60.12 50.0 LT	15	
63+28.50 32.2 RT		38
66+52.59 -80.0 LT	5	
69+52.21 53.2 LT	5	
69+63.24 50.9 LT	8	
69+76.76 52.9 LT	15	
70+42.80 51.5 LT		19
71+09.14 51.0 LT	15	
71+22.70 51.5 LT	8	
71+49.64 46.6 LT	15	
71+67.68 61.6 RT	8	
71+82.14 62.9 RT	8	
71+89.03 48.3 LT	8	
71+98.14 47.8 LT	8	
72+46.83 59.9 RT	5	
72+67.28 49.8 LT	10	
72+68.08 61.9 RT	5	
72+79.42 57.8 RT	5	
72+92.35 60.5 RT	5	
73+17.73 58.3 RT	8	
74+01.72 55.3 RT	8	
74+15.03 54.5 RT	8	
74+29.17 58.7 RT	8	
74+50.80 61.6 RT	5	
75+39.87 50.7 LT	13	
76+44.32 45.4 LT	13	
76+45.58 49.4 LT	5	
78+27.66 40.2 RT	5	
78+74.30 40.1 RT	5	
79+19.58 39.8 RT	5	
79+66.54 38.6 RT	5	
85+77.44 42.3 RT	15	
TOTAL	406	79

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EARTH EXCAVATION ADJ. FOR SHRINKAGE (CU YD)	SECTION TOTALS EMBANKMENT (CU YD)	EARTHWORK BALANCE WAST(+) OR SHORTAGE (-) (CU YD)
Douglas Road					
19+45.00 - 23+07.21	301	45	192	0	192
23+07.21 - 33+52.58	1264	190	806	336	470
33+52.58 - 43+02.59	2665	400	1699	227	1472
43+02.59 - 46+72.90	1511	227	963	415	548
46+72.90 - 54+24.03	1660	249	1058	2516	-1458
54+24.03 - 66+37.47	2936	440	1872	2702	-830
66+37.47 - 74+98.81	3214	482	2049	1066	983
74+98.22 - 80+04.51/80+28.14	1490	224	950	643	307
80+04.51/80+28.14 - 83+34.53	1054	158	672	48	624
83+34.53 - 87+91.93	1151	173	734	141	593
TOTAL	17245	2585	10995	8095	2900

SHRINKAGE FACTORS
EARTH EXCAVATION = 25%
TOPSOIL = 15%

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. 2508 - DOUGLAS ROAD
(U.S. RTE 34 TO U.S. RTE 30)
**TREE REMOVAL SCHEDULE
& TREE REPLACEMENT SCHEDULE
& EARTHWORK SCHEDULE**

SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY BAH
CHECKED BY CRF

PLAN SURVEYED BY _____ DATE _____
ALIGNED CHECKED BY _____
RT. OF WAY CHECKED BY _____
NO. _____
NOTE BOOK NO. _____

PROFILE SURVEYED BY _____ DATE _____
EARTHWORK CHECKED BY _____
STRUCTURE NOTATIONS CHECKED BY _____
NO. _____
NOTE BOOK NO. _____

2-4-2007 AM
3/28/2007
y:\jobs\smith\2006\010742_douglas\ced\fn.dwg\142_sch08_tree.dgn