

SUMMARY OF QUANTITIES

F. A. D. DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315		FULTON	324	6
STA.	TO STA.		FED. AID PROJ. NO. 5	
			BALANCE	

*109W-1RS-2;110W-RS-1

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	_8Q/2Q_ 1000	_8Q/2Q_ Y080	100%_SI 1000	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	_8Q/2Q_ 1000	_8Q/2Q_ Y080	100%_SI 1000
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	158	158			X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD) 11.4% #50	TON	2011	2011		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	543	543			40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	229	229		
20100500	TREE REMOVAL, ACRES	ACRE	2.85	2.85			40600990	TEMPORARY RAMP	SO YD	85	85		
20200100	EARTH EXCAVATION	CU YD	71,777	71,777			40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4021	4021		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	898	898			40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	59	59		
20700110	POROUS GRANULAR EMBANKMENT	TON	174	174			44000100	PAVEMENT REMOVAL	SO YD	185	185		
20800150	TRENCH BACKFILL	CU YD	247	247			44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	47,926	47,926		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	800	800			44000400	GUTTER REMOVAL	FOOT	7501	7501		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	104,347	104,347			44004000	PAVED DITCH REMOVAL	FOOT	200	200		
21400110	GRADING AND SHAPING DITCHES	UNIT	4.6	4.6			44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	1752	1752		
*25000210	SEEDING, CLASS 2A	ACRE	21.5	21.5			44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	324	324		
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1935	1935			44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	1236	1236		
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1935	1935			44300900	REFLECTIVE STRIP CRACK CONTROL TREATMENT SYSTEM A	FOOT	7741	7741		
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1935	1935			48101200	AGGREGATE SHOULDERS, TYPE B	TON	1470	1470		
*25100115	MULCH, METHOD 2	ACRE	21.5	21.5			50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
*25100630	EROSION CONTROL BLANKET	SO YD	580	580			50102400	CONCRETE REMOVAL	CU YD	27	27		
*25101400	STRAW MULCH	TON	43	43			50104300	CONCRETE HEADWALL REMOVAL	CU YD	9.8	9.8		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2150	2150			50104400	CONCRETE HEADWALL REMOVAL	EACH	42	42		
28000300	TEMPORARY DITCH CHECKS	EACH	167	167			50105220	PIPE CULVERT REMOVAL	FOOT	545.0	545.0		
28000400	PERIMETER EROSION BARRIER	FOOT	16,862	16,862			50200100	STRUCTURE EXCAVATION	CU YD	313	313		
28000500	INLET AND PIPE PROTECTION	EACH	11	11			50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	27,818	27,818		
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	1867	1867									
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	2656	2656			54003000	CONCRETE BOX CULVERTS	CU YD	140.8	140.8		
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	2561	2561			54010202	PRECAST CONCRETE BOX CULVERT 2' X2'	FOOT	109.0	109.0		
28100811	STONE DUMPED RIPRAP, CLASS A6	TON	63	63			54010302	PRECAST CONCRETE BOX CULVERT 3' X2'	FOOT	54.0	54.0		
28102630	STONE RIPRAP DITCH CHECKS	EACH	43	43			54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	335.0	335.0		
28200200	FILTER FABRIC	SO YD	5056	5056			54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	189.0	189.0		
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	548	548			542JA048	PIPE CULVERTS, CLASS A 48" (JACKED)	FOOT	92.0	92.0		
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SO YD	185	185			54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	52.0	52.0		
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SO YD	6052	6052			54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	300.0	300.0		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1263	1263			54201285	PIPE CULVERTS, TYPE 2 RCCP 30"	FOOT	121.0	121.0		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	580	580			54202125	PIPE CULVERTS, TYPE 3 RCCP 30"	FOOT	80.0	80.0		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	25	25			54202983	PIPE CULVERTS, TYPE 4 RCCP 48"	FOOT	32.0	32.0		
40600300	AGGREGATE (PRIME COAT)	TON	145	145			54213453	END SECTIONS 18"	EACH	16	16		