CONTRACT NO. 88518

F. A. S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
315	-	FULTON	324	7
STA.		TO STA.		
FED. ROAD DIST. NO. 9	ILLINOIS	FED. AID PROJECT		

+109W-1,RS-2;110W,RS-1

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		_80/20_ I000	_80/20_ Y080	100%_SI I000
54213459	END SECTIONS 24"	EACH	8	8		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	10	10		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	6	6		
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2		
54248510	CONCRETE COLLAR	CU YD	1.9	1.9		
60109621	BACKSLOPE DRAINS, TYPE 2 6"	FOOT	450	450		
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	1	1		
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	5550	5550		
60603400	GUTTER OUTLET (SPECIAL)	EACH	9	9		
60603450	GUTTER INLET (SPECIAL)	EACH	8	8		
60900505	CONCRETE THRUST BLOCKS (SPECIAL)	EACH	1	1		
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	104	104		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	207	207		
66700205	PERMANENT SURVEY MARKERS - TYPE I	EACH	26	26		
66700305	PERMANENT SURVEY MARKERS - TYPE II	EACH	2	2		
66700605	PERMANENT SURVEY TIES	EACH	20	20		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
67000600	ENGINEERS FIELD LABORATORY	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	46	46		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4683	4683		
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	49,063	49,063		
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	62	62		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	520	520		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425	425		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425	425		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	49,063	49,063		
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	62	62		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		_80/20_ I000	_80/20_ Y080	100%_SI I000
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	195	195		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	165	165		
89502380	REMOVE EXISTING HANDHOLE	EACH	1	1		
* K1005431	SEEDLING MIXTURE "A"	UNIT	10.5	10.5		
X0301245	SHOULDER REMOVAL	SQ YD	426	426		
X0322729	MATERIAL TRANSFER DEVICE	TON	4021	4021		
X0323260	SEDIMENT BASIN	EACH	1	1		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2376	2376		
X0545000	BOX CULVERT REMOVAL	FOOT	86	86		
X0914000	PRECAST CONCRETE BOX CULVERT END SECTIONS 2' X2'	EACH	6	6		
X0914100	PRECAST CONCRETE BOX CULVERT END SECTIONS 3' X2'	EACH	2	2		
* X2503100	MOWING	UNIT	319			319
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	1	1		
X8900030	REMOVE EXISTING TEMPORARY TRAFFIC SIGNAL EQUIPMENT	EACH	1	1		
X8950095	REMOVE EXISTING CONTROL INSTALLATION, AND SALVAGE	EACH	1	1		
XX004033	CLEAN EXISTING CULVERTS	EACH	1	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0015500	DEBRIS REMOVAL	L SUM	1	1		
Z0022800	FENCE REMOVAL	FOOT	10,796	10,796		
Z0023500	FILLING EXISTING CULVERTS	CU YD	99.2	99.2		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	EACH	4	4		
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	4	4		
Z0004500	BITUMINOUS DRIVEWAY PAVEMENT 8"	SQ YD	366	366		
Z0054500	ROCK FILL	TON	3046	3046		
Z0055300	RUMBLE STRIP	EACH	2	2		
Z0076600	TRAINEES	HOUR	500		500	
35600718	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/2"	SQ YD	1726	1726		
X0325895	MANHOLES, TYPE A, SPECIAL, 8'-DIAMETER	FOOT	23.9	23.9		