


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315		FULTON	324	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*109W-1,RS-2;110W,RS-1



TYPICAL SECTION #5
US 136

STA. 533+36.87 TO STA. 538+35.40 LT
STA. 533+33.85 TO STA. 537+85.80 RT

- ① EX. 9-6-9 PCC PAVEMENT
- ② EX. BITUMINOUS WIDENING 9"
- ③ EX. AGGREGATE SHOULDER
- ④ EX. BITUMINOUS OVERLAY
- ⑤ EX. BITUMINOUS OVERLAY 2"
- ⑥ EX. STRIP REFLECTIVE CRACK CONTROL
- ⑦ EX. TYPE A GUTTER
- ⑧ EX. TYPE B GUTTER
- ⑨ PR. HOT MIX ASPHALT SURFACE REMOVAL (COLDMILLING) 1 1/2"
- ⑩ PR. POLYMERIZED LEVELING BINDER (MM), N50 3/4"
- ⑪ PR. HOT MIX ASPHALT SURFACE CSE. MIX D, N50 1 1/2"
- ⑫ PR. HOT MIX ASPHALT BASE COURSE 10 1/2"
- ⑫A PR. HOT MIX ASPHALT BASE COURSE WIDENING 10 1/2"
- ⑬ PR. AGGREGATE SHOULDER TY. B (RAP)
- ⑭ PR. TY. A GUTTER (MODIFIED)
- ⑮ PR. FURN. AND PLACE TOPSOIL 4"
- ⑯ PR SUBBASE GRANULAR MATERIAL, TYPE B (VARIABLE DEPTH)
- ⑰ PR INCIDENTAL BITUMINOUS SURFACING 2 1/2"
- ⑱ PR AGGREGATE SURF. COURSE, TYPE B (VAR. DEPTH)

- PR HMA BASE CSE 10 1/2" OR HMA BASE CSE WIDENING 10 1/2" SHALL BE PLACED PRIOR TO PR HMA SURFACE REMOVAL AND PR OVERLAY
- PR STONE DUMPED RIPRAP TO BE PLACED IN FLOWLINE AT LOCATIONS SHOWN IN THE PLANS PER DISTRICT STANDARD 281001
- EMBANKMENT SHALL BE USED TO FILL VOID BENEATH PR. HMA BASE CSE. OR PR. HMA BASE CSE. WIDENING CAUSED BY GUTTER REMOVAL. AN ADDITIONAL 1.0 FT. OF PAVEMENT WILL BE REMOVED WITH THE GUTTER SECTION. SEE GUTTER REMOVAL SPECIAL PROVISION.

PLOT DATE = 9/15/2007
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = mshar-05e

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROPOSED TYPICAL SECTION
 US 136
 SCALE: VERT. DRAWN BY CEM
 HORIZ. CHECKED BY CEM
 DATE 08/09/05