

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315		EULION	324	21
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

*109W-1,RS-2;110W,RS-1

TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
LOCATION	UNITS
LT. STA. 589+65	7
LT. STA. 589+65	6
LT. STA. 615+20	6
LT. STA. 615+50	7
LT. STA. 616+50	8
LT. STA. 621+00	11
LT. STA. 621+30	6
LT. STA. 629+75	15
LT. STA. 636+45	10
LT. STA. 636+45	10
LT. STA. 638+05	10
LT. STA. 638+05	13
LT. STA. 638+65	8
RT. STA. 507+20	7
RT. STA. 507+20	6.5
RT. STA. 569+50	6
RT. STA. 656+90	8
RT. STA. 657+00	13
TOTAL	158

TREE REMOVAL (OVER 15 UNITS DIAMETER)	
LOCATION	
LT. STA. 510+10	31
LT. STA. 525+30	31
LT. STA. 538+25	59
LT. STA. 624+90	30
LT. STA. 625+20	26
LT. STA. 631+25	20
LT. STA. 631+55	23
LT. STA. 636+10	19
LT. STA. 638+60	38
LT. STA. 651+80	43
RT. STA. 507+85	24
RT. STA. 641+80	31
RT. STA. 649+05	27
RT. STA. 649+10	23
RT. STA. 650+80	34
RT. STA. 656+50	43
RT. STA. 656+70	41
TOTAL	543

TREE REMOVAL, ACRES	
LOCATION	ACRE
LT. STA. 602+00.00 TO STA. 603+50.00	0.2118
LT. STA. 603+69.00 TO STA. 611+38.00	0.2009
LT. STA. 612+36.00 TO STA. 614+29.15	0.0490
LT. STA. 617+25.30 TO STA. 620+75.45	0.1063
LT. STA. 626+50.00 TO STA. 629+00.00	0.5393
LT. STA. 636+86.25 TO STA. 637+63.35	0.0120
LT. STA. 639+00.00 TO STA. 645+00.00	0.7486
LT. STA. 654+50.00 TO STA. 658+00.00	0.1139
RT. STA. 538+22.00 TO STA. 540+58.50	0.1908
RT. STA. 583+50.00 TO STA. 586+50.00	0.4232
RT. STA. 588+00.00 TO STA. 592+00.00	0.1932
RT. STA. 600+00.00 TO STA. 602+00.00	0.0627
TOTAL	2.85

PAVEMENT REMOVAL	
LOCATION	SO. YD.
STA. 539+54.90	185
TOTAL	185

GUTTER REMOVAL	
LOCATION	FOOT
LT. STA. 533+36.87 TO STA. 538+35.40	498.5
LT. STA. 540+00.00 TO STA. 543+00.00	300.0
LT. STA. 578+67.00 TO STA. 582+78.85	412.0
LT. STA. 586+96.00 TO STA. 597+00.00	1004.0
LT. STA. 605+50.00 TO STA. 612+51.00	701.0
LT. STA. 651+43.00 TO STA. 655+00.00	357.0
RT. STA. 533+33.85 TO STA. 537+85.80	452.0
RT. STA. 540+00.00 TO STA. 543+00.00	300.0
RT. STA. 578+67.00 TO STA. 583+17.95	451.0
RT. STA. 586+96.00 TO STA. 597+00.00	1004.0
RT. STA. 605+50.00 TO STA. 612+51.00	701.0
RT. STA. 642+30.00 TO STA. 655+50.00	1320.0
TOTAL	7,501

REMOVAL OF EXISTING STRUCTURES	
LOCATION	EACH
STA. 539+54.90	1
TOTAL	1

CONCRETE REMOVAL	
LOCATION	CU. YD.
LT. STA. 584+11.00	4.0
TOTAL	4.0

SEE STRUCTURE PLANS FOR ADDITIONAL QUANTITIES

SHOULDER REMOVAL	
LOCATION	SQ. YD.
LT. STA. 537+88.25 TO STA. 541+25.75	187.5
LT. STA. 601+23.18 TO STA. 602+35.18	49.8
RT. STA. 537+98.65 TO STA. 541+11.15	138.9
RT. STA. 601+23.18 TO STA. 602+35.18	49.8
TOTAL	426

REMOVE EXISTING HANDHOLE	
LOCATION	EACH
RT. STA. 514+00.00	1
TOTAL	1

REMOVE EXISTING CONTROL INSTALLATION, AND SALVAGE	
LOCATION	EACH
RT. STA. 514+00.00	1
TOTAL	1

DEBRIS REMOVAL	
LOCATION	L. SUM
LT. STA. 640+50.00	1
TOTAL	1

PAVED DITCH REMOVAL	
LOCATION	FOOT
RT. STA. 583+20.00 TO STA. 585+20.00	200
TOTAL	200

FENCE REMOVAL	
LOCATION	FOOT
LT. STA. 499+70.00 TO STA. 502+65.00	295.00
LT. STA. 504+23.55 TO STA. 510+50.00	626.45
LT. STA. 538.00.00 TO STA. 538+45.00	45.00
LT. STA. 539+42.30 TO STA. 543+29.30	433.00
LT. STA. 547+00.00 TO STA. 550+24.00	324.00
LT. STA. 550+73.00 TO STA. 551+00.00	27.00
LT. STA. 555+49.75 TO STA. 556+73.80	124.05
LT. STA. 557+00.00 TO STA. 565+00.00	800.00
LT. STA. 572+91.75 TO STA. 577+53.00	461.25
LT. STA. 580+40.00 TO STA. 587+00.00	660.00
LT. STA. 587+49.50 TO STA. 594+30.90	681.40
LT. STA. 597+22.50 TO STA. 598+04.00	81.50
LT. STA. 600+00.00 TO STA. 603+65.40	365.40
LT. STA. 614+23.50 TO STA. 616+37.70	214.20
LT. STA. 617+32.40 TO STA. 622+61.90	529.50
LT. STA. 642+50.00 TO STA. 647+00.00	450.00
LT. STA. 645+87.00 TO STA. 646+55.00	68.00
RT. STA. 571+49.20 TO STA. 577+73.65	624.45
RT. STA. 580+49.40 TO STA. 603+60.00	2310.60
RT. STA. 617+56.50 TO STA. 618+08.40	51.90
RT. STA. 637+50.00 TO STA. 642+23.00	473.00
RT. STA. 643+59.55 TO STA. 650+67.30	707.75
RT. STA. 653+94.85 TO STA. 654+34.00	39.15
RT. STA. 655+08.00 TO STA. 658+00.00	292.00
CARLS LANE	
LT. STA. 8+49.60 TO STA. 9+59.00	109.40
TOTAL	10,796

STEEL PLATE BEAM GUARDRAIL REMOVAL	
LOCATION	FOOT
LT. STA. 627+17.20 TO STA. 628+19.25	104
TOTAL	104

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. NONE
HORIZ. DATE 02/07/2007

DRAWN BY CEM
CHECKED BY CEM