SIGN

LOCATION	SIGN CODE	SIGN PANEL - TYPE 1	WOOD SIGN SUPPORT
		SQ FT	FOOT
STATE STREET			
	W2-6	6.25	14.5
	W16-12P	5.00	
29+02.50	R4-7	5.00	14.5
29+09.16	W11-2	6.25	14.5
29+26.23	W11-2	6.25	14.5
29+39.79	R1-2	3.125	14.5
29+45.51	R1-2	3.125	14.5
29+45.51	D3	1.33	
29+45.51	D3	1.33	
29+85.22	R6-1R	3.00	13.0
30+14.78	R6-1R	3.00	13.0
30+54.48	R1-2	3.125	14.5
30+54.48	D3	1.33	
30+54.48	D3	1.33	
30+59.06	R1-2	3.125	14.5
30+70.86	W11-2	6.25	14.5
30+91.84	W11-2	6.25	14.5
30+97.51	R4-7	5.00	14.5
	W2-6	6.25	14.5
	W16-12P	5.00	
GREENMOUNT			
	W2-6	6.25	14.5
	W16-12P	5.00	
39+02.49	R4-7	5.00	14.5
39+11.38	W11-2	6.25	14.5
39+28.85	W11-2	6.25	14.5
39+41.12	R1-2	3.125	14.5
39+45.99	R1-2	3.125	14.5
39+45.99	D3	1.33	
39+85.22	R6-1R	3.00	13.0
OBERNUEFEMANN			
40+14.78	R6-1R	3.00	13.0
40+53.93	R1-2	3.125	14.5
40+53.93	D3	1.33	
40+60.49	R1-2	3.125	14.5
40+69.04	W11-2	6.25	14.5
40+90.63	W11-2	6.25	14.5
40+96.00	W10-1	9.00	15.0
41+59.05	R8-8	5.00	14.5
41+70.66	R4-7	5.00	14.5
42+33.82	R8-8	5.00	14.5
	W2-6	6.25	14.5
	W16-12P	5.00	
	W10-1	9.00	15.0
	TOTAL:	188	459

EARTHWORK

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	SHRINKAGE FACTOR	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD		CU YD	CU YD
STATE STREET					
28+18.52 TO 31+76.54	99	78	25	178	-100
GREENMOUNT					
39+00.00 TO 39+50.00	17	13	25	7	6
OBERNUEFEMANN					
40+50.00 TO 41+73.95	25	20	25	21	-1
TOTAL:	141	111		206	-95

EROSION CONTROL

LOCATION	SIDE	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
		FOOT	EACH
28+63.21 (STATE STREET) TO 39+00.00 (GREENMOUNT	SW QUADRANT	147	
29+12.38 (STATE STREET)	LT		1
29+12.38 (STATE STREET)	RT		1
29+14.04 (STATE STREET) TO 41+73.95 (OBERNUEFEMANN)	NW QUADRANT	184	
29+27.29 (STATE STREET)	LT		1
29+27.36 (STATE STREET)	RT		1
29+67.66 (STATE STREET)	LT		1
31+02.84 (STATE STREET)	LT		1
31+02.94 (STATE STREET)	RT		1
31+25.00 TO 31+76.54 (STATE STREET)	RT	53	
39+10.00 (GREENMOUNT)	LT		1
39+10.00 (GREENMOUNT)	RT		1
39+40.00 (GREENMOUNT)	LT		1
39+40.00 (GREENMOUNT)	RT		1
39+50.00 (GREENMOUNT)	LT		1
39+57.57 (GREENMOUNT)	RT		1
40+53.28 (OBERNUEFEMANN)	RT		1
40+56.00 (OBERNUEFEMANN)	LT		1
40+60.00 (OBERNUEFEMANN)	RT		1
41+73.95 (OBERNUEFEMANN) TO 31+75.00 (STATE STREET)	NW QUADRANT	267	
TOTAL:		651	16

CITY OF O'FALLON, ILLINOIS

SCHEDULE OF QUANTITIES

SHEET 4 OF 6

SCALE: N/A
DATE: 10/05/06
DRAWN BY: KMO
CHECKED BY: SSM