INDEX

SUMMARY OF QUANTITIES, GENERAL NOTES AND UTILITY REFERENCES	2
NAME PLATE, CONSTRUCTION SIGN AND BENCH MARK	_, 3
GENERAL PLAN, REFERENCE NOTES, R.O.W. AND RIPRAP	4
PROPOSED ROADSIDE DITCH IMPROVEMENT, PLAN-PROFILE	5-6
3 MILE LANE, GENERAL PLAN AND CULVERT DETAILS	7
ILL. ROUTE 125, GENERAL PLAN AND CULVERT DETAILS	8
ILL. ROUTE 125, 3 MILE LANE, FREMONT ST., CEM. RD., TRAFFIC CONTROL $__$	9
ILL. ROUTE 125, CULVERT END SECTION DETAILS (UPSTREAM END)	10
ILL. ROUTE 125, CULVERT END SECTION DETAILS (DOWNSTREAM END)	_11
FREMONT STREET, GENERAL PLAN AND CULVERT DETAILS	12
ABANDONED R.R. CROSSING GENERAL PLAN	13
CEMETERY ROAD GENERAL PLAN AND CULVERT DETAILS	14
CEMETERY ROAD CULVERT HEADWALL DETAILS	15
CEMETERY ROAD CULVERT HEADWALL DETAILS	_16
DETAILS	_17-19
EROSION CONTROL PLAN	20
EROSION CONTROL GENERAL NOTES	_20A
ROADSIDE DITCH CHANNEL CROSS SECTIONS (ALONG ILL. RTE. 125)	21-22
CHANNEL CROSS SECTIONS (SOUTH OF EREMONT STREET)	23

STATE OF ILLINOIS DEPARTMENT OF NATURAL RESOURCES OFFICE OF WATER RESOURCES




REGIONAL MAP

D.O.T. STANDARDS

000001	Standard Symbols, Abbreviations, and Patterns
280001	Temporary Erosion Control Systems
442201	Class C And D Patches
515001	Name Plate For Bridges
542301	Precast Reinforced Concrete Flared End Section
601101	Concrete Headwall For Pipe Drain
666001	Right Of Way Markers
701001	Off-Rd Operations 2L, 2W, More Than 15' (4.5 m) Away
701006	Off-Rd Operations 2L, 2W, 15' (4.5 M) To 24" (600 mm) to Pavement Edge
701901	Traffic Control Devices
B.L.R. 21-5	Typical Application Of Traffic Control Devices For Construction On Rural Local Highways
701201	Lane Closure 2L, 2W Day Only Speeds ≥ 45 MPH
701311	Lane Closure 2L, 2W Moving Operations - Day Only

ASHLAND FLOOD CONTROL PROJECT

ASHLAND, ILLINOIS
CASS COUNTY
FR-399
2013



Montrey 12/11/12

LICENSE EXPIRES 11-30-14

ILLINOIS REGISTERED PROFESSIONAL ENGINEER NO. 062-049591
LICENSE EXPIRES 11-30-13

APPROVED BY Color DATE 12-13-12

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	24
20200100	EARTH EXCAVATION	CU YD	8,180
20300100	CHANNEL EXCAVATION	CU YD	140
21101625	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,994
25100900	TURF REINFORCEMENT MAT	SQ YD	272
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	365
28000305	TEMPORARY DITCH CHECKS	FOOT	130
28000400	PERIMETER EROSION BARRIER	FOOT	113
28000500	INLET AND PIPE PROTECTION	EACH	1
28100105	STONE RIPRAP. CLASS A3	SQ YD	557
28100107	STONE RIPRAP, CLASS A4	SO YD	471
28100109	STONE RIPRAP, CLASS A5	SQ YD	1,105
28200200	FILTER FABRIC	SQ YD	1 , 576
44000100	PAVEMENT REMOVAL	SQ YD	48
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	199
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	50
*50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
*50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
*50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	4
*50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1
50102400	CONCRETE REMOVAL	CU YD	5.2
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2387
51100300	SLOPE WALL 6 INCH	SQ YD	120
51500100	NAME PLATES	EACH	1
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	4
54003000	CONCRETE BOX CULVERTS	CU YD	37.8
54010404	PRECAST CONCRETE BOX CULVERTS 4'x4'	FOOT	110.5
54010604	PRECAST CONCRETE BOX CULVERTS 6'x4'	FOOT	90
54021004	PRECAST CONCRETE BOX CULVERTS 10'x4'	FOOT	54
542D0213	PIPE CULVERTS, CLASS D, TYPE 1 8" (GALVANIZED AND COATED CMP)	FOOT	12
542D0215	PIPE CULVERTS, CLASS D, TYPE 1 10" (GALVANIZED AND COATED CMP)	FOOT	12
542A1081	PIPE CULVERTS, CLASS A (RCCP), TYPE 2, 36"	FOOT	90
542A1093	PIPE CULVERTS, CLASS A (RCCP), TYPE 2, 48"	FOOT	77
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4
*67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	8
67100100	MOBILIZATION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	460
70301000 *	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	172
*	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM FOOT	1
*	NON-RESTRICTIVE FENCE		44
~ *	SEEDING, MULCHING, AND FERTILIZING	ACRE L SUM	3.71
*	CONSTRUCTION STAKING	CU YD	1
59300100 *	CONTROLLED LOW-STRENGTH MATERIAL WOOD INFORMATION SIGNS		207 30
	WOOD INFORMATION SIGNS	SQ FT	30

* INDICATES NON-STANDARD ITEM COVERED BY PLANS AND/OR SPECIAL PROVISION

	SCHEDULE OF EARTHWORK								
LOCATION	CHANNEL EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACEMENT (NOT PAID FOR) (CU YD)	EARTH EXCAVATION (CU YD)					
2+17 - 2+71				56					
3+25 - 12+00		962	877	4,659					
12+00 - 22+20		986	829	<i>3,4</i> 65					
Freemont Street (Sheet 12)	10	18	15.5						
Cemetery Road (Sheet 14)	48	28	24						
Abandoned R.R. Crossing (Sht. 13)	82								
TOTAL	140	1,994	1,745.5	8,180					

GENERAL NOTES

- 1. All elevations refer to N.G.V.D. (National Geodetic Vertical Datum).
- 2. The Contractor shall furnish, erect, and when directed by the Engineer, completely remove two construction signs. The exact location of the signs shall be determined by the Engineer in the field.
- 3. Reinforcement bars shall conform to the requirements of AASHTO M-31, or M-322 Grade 60.
- 4. All construction joints shall be bonded unless otherwise noted.
- 5. Class SI Concrete shall be used throughout. All exposed edges of concrete shall be beveled $\frac{3}{4}$ " unless otherwise shown in the plans.
- 6. All lateral drainage that exists prior to construction shall be restored as shown on the plans and/or as directed by the Engineer. Unless otherwise specified, all costs of restoration shall be considered included with the Contract and no additional compensation will be allowed.
- 7. All construction operations shall be contained within the easement area or work limits as indicated on the plans. It shall be the full responsibility of the Contractor to secure all rights of ingress and egress to said Right-of-Way including the satisfactory protection and restoration of property as required in Art. 107.20 and 107.23 of the Standard Specifications.
- 8. The location, maintenance, removal, and restoration to original condition of all haul roads shall be approved by the Engineer and all cost shall be considered included in the Contract.
- 9. The Contractor shall call J.U.L.I.E. (800-892-0123) for the location of existing utilities 48 hours prior to beginning construction.
- 10. Prior to beginning work in the vicinity of the utilities, the Contractor shall contact the respective owners as shown on this sheet and shall schedule work so as not to interfere with any required adjustments.
- 11. With the exception of those utilities designated on the plans to be adjusted by the Contractor, all existing utilities affected by the construction operations shall be adjusted by others. Utilities which do not require adjustment shall be protected and not disturbed. All costs of protection shall be considered included in the Contract, and no additional compensation will be allowed.
- 12. All unsuitable material and excess excavation shall be disposed of at locations provided by the Contractor at his expense. The locations shall be inspected and approved by the Engineer.
- 13. Channel excavation shall include the cost of removing and disposing of existing riprap, brick, block, rubble, etc.
- 14. All open excavations are to be surrounded with a 4'-0" construction fence during non-working hours. The fence materials are to meet the approval of the Engineer. Cost of the fence shall be included in the contract.
- 15. All dewatering costs shall be included in the contract.
- 16. The Contractor shall notify the Village of Ashland and the Ashland Township concerning the closing of streets and shall conform to all requirements so specified without additional cost to the State.
- 17. The Contractor shall submit his proposed method of maintaining channel flows, for approval by the Engineer, prior to beginning construction.
- 18. Plan dimensions and details relative to the existing structures have been taken from existing plans and/or past surveys and reports, and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit bid price for the work.
- 19. It is the intention of this Contract that disruption to traffic on II Rte 125, 3 Mile Lane, Fremont St. and Cemetery Rd. is limited to the shortest reasonable time. At all times, either Fremont St. or Rte. 125 shall be completely open to traffic. Prior to starting work on either road, the Contractor shall submit to the Engineer for approval a satisfactory progress schedule in accordance with Article 108.02 of the Standard Specifications. A reasonable number of working days shall also be submitted for approval for each culvert.
- 20. The Contractor shall notify IDOT District 6 Bureau of Operations at (217) 782-7314 14 days in advance of the IL. Route 125 road closure. This closure is restricted to 5
- 21. Prior to the beginning of work in the vicinity of the utilities, the Contractor shall contact the owners listed in the utility reference table and schedule work so as not to interfere with required adjustments.

	REMOVAL OF EXISTING STRUCTURES								
No.	Station	Туре	Description	Each					
1	Sta. 3+00±	Culvert	48" Dia. CMP with Reinforced Concrete Headwalls	1					
2	Sta. 2+06±	Culvert	6'x4' Reinforced concrete Box Culvert	1					
3	Sta. 21+95±	End Section	End Sections to be Removed From 36" RCP's	4					
4	North Side Cemetery Rd.	Retaining Wall	Concrete Retaining Wall	1					

OFFICE OF WATER RESOURCES


PRECAST BOX CULVERT SCHEDULE (ASTM C1577)									
	Size		Design fill	(Ft.)	PGE Backfill				
Station	(Span x height)	Skew**	Edge of shldr. (Min.)	Мах.	required				
2+06.25 Fremont St.	Double 6' x 4'	6°	1.54′	1.7′	Yes				
1047+96.17 IL. Rte. 125	Single 4' x 4'	45°	4.00′	4.18′	Yes				
Three Mile Lane	Single 10' x 4'	0°	2.05′	2.36′	Yes				

^{**} The skew is the angle between a perpendicular line to the box culvert and the centerline of the roadway

UTILITY REFERENCE TABLE

J.U.L.I.E.	Call 48 hours prior to construction	(800) 892-0.
Village of Ashland	Dave Handy, Village President Village of Ashland 101 Yates Street Ashland, Illinois 62612	(217) 476-33
Ashland Township	Jim Mitchell, Ashland Road Commissioner	(217) 476-88
Telephone	James Mansfield, Design Engineer Ameritech Engineering Division 529 S. Seventh St. Floor 3E	(217) 789-86
	Springfield, IL 62721	Fax (217) 789-510
Telephone	G. R. Mansfield, Plant Supervisor Cass County Telephone Co. #1 Redbud Road, P.O. Box 230	(217) 452-30
	Virginia, IL 62691	Fax (217) 452-70
Electric	Gordon Tingley, Senior Transmission Engineer Central Illinois Public Service Division Office 104 East Third St. Beardstown, Illinois 62618	(217) 323-21
Gas	Willard Bohlmann Central Illinois Public Service Division Office 104 East Third St. Beardstown, Illinois 62618	(217) 323-21 EXT. 263
Water Sewer	Dave Troxel P.O. Box 170 Ashland, Illinois 62612	(217) 476-33
Cable TV	No Facilities in the area	

FR-399



6' X 4' RC-BOX

60" & CMP

1.48

1.61

46.6

32.2

342

349

627.5

620.13

598(PMP)

396

800

250

628.88

629.2

CONSTRUCT 48" RCCP CULVERT WITH CAST IN PLACE HEADWALLS

(DOWNSTREAM PROJECT LIMITS)

SEE SHEET 14-16.

FREMONT STREET

CEMETERY ROAD

STONE RIPRAP, CLASS A4

STONE RIPRAP, CLASS A5

FILTER FABRIC

445

430


875


FR-399


SQ.YD.


SQ.YD.


SQ.YD.





























BARS v to v3

O:\OwrProjImpl\Projects\ASHLANDI\Plan Sheets\sheet 16.dgn

TMM RLP





GENERAL NOTES

All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).

All dimensions are in inches unless otherwise shown.

All exposed edges of concrete shall be beveled $\frac{3}{4}$ ".


Class SI Concrete shall be used throughout.

Reinforcement Bars shall conform to the requirements of A.A.S.H.T.O. M-31, or M-322, Grade 60.

*BILL OF MATERIAL

Bar	No.	Size	Length	Shape
а	16	#5	1'-6"	
bз	4	#5	15'-3"	
<i>b</i> 7	2	#4	17'-2"	
b9	2	#5	20′-5"	
b12	2	#4	23'-8"	
b13	2	#4	26'-11"	
b14	4	#4	29'-6"	
d	38	#4	4'-3"	
h	4	#5	36′-7"	
h ₁₄	4	#4	8'-3"	
h ₁₅	4	#4	12′-6"	
V	12	#4	8'-6"	
V1	10	#4	7′-6"	
V2	12	#4	6'-6"	
V3	14	#4	5'-4"	
W	4	#4	4'-0"	
EINFOF POXY C	RCEMENT COATED	BARS,	POUND	**907
ONCRET	re Box (CULVERT.	S CU YD	23.9
D:11 - F 1	1-4		F b - + b	Cad Cast

- * Bill of Material accounts for both End Sections.
- ** 57 lbs. of Welded Wire Fabric is included in this quantity.





PROJECT Water Rcs		BRIDGI	E 6 2	x 4	R 8 W of the 3		e		. 1 o 07/96
ROUTE IL 125					ont Street and	Bored B	у М.	Tapp	an
sec. not assigned		STA.	619+00	0	Ch	ecked B	у Т.	Ripk	a
COUNTY Cass	-				Surf Wat El. Grndwater El.	622.2			
Boring No. 2 Sta 619+22 O/8 14' R	El.	N	Qu t/sf	W %	at Compl At 24 Hrs	608.1	E1.	N	Qu t/sf
Ground Surface 628. Grey & Brown, Moist SILTY CLAY Fill	1 0		-	-	Grey, Moist CLAY LOAM T	i11			
							_	3	
						_	-25	11 _17_	8.2 S_13
	_	1_					_		
622	- 5	3_	1.5 B	26					
Grey & Brown, Moist	· <u> </u>	1					_		
SILTY CLAY		-1- 3	1.0 B	25				-8 -20	10+
						_	-30	_32_	_S_13
Grey, V. Moist			0.4	32			_		
617	- <u>10</u>	2_	B	-			_		
Grey & Brn, V. Moist SILTY CLAY LOAM	_		0.3	32				11	
		_1_1_	_в				-35	-22	10+ S 13
Grey & Dk Brn, Mois		0_					_		
SILTY CLAY	-15	3_	1.4 B	25					
612	.1	,							
Grey & Brn, Moist CLAY LOAM water gastropod shells	· _	-1- 1	0.5 B	26				6_	8.0
Grey, Moist	.1				Boring Comple	588.1 ted	-40	_20_	B
CLAY LOAM Till	_	0-	0.5	23			_		
•	-20	3_	В						
		3_	3.5	13	-		_		
Grey & Brown		9	3.5 B	13			-45		


BORINGS AT PROPOSED CULVERT - FREMONT ST.

BORINGS AT PROPOSED CULVERT -

ILLINOIS DEPARTMENT District Six Mater: SE 1/4, N	ials					R 8	Wo	the 3rd	Bori	ng L	oundai og . 1 oi	
PROJECT Water Rcs	_ E	RIDG	Sout	x 4	OOX CI	le L	rt ne	Dat	e		05/96	
ROUTE IL 125					and			Bored B	у <u>М.</u>	Tapp	an	
SEC. 3X, 3RS	£	TA.	1047+	90			_ cı	necked B	у <u>т.</u>	Ripk	a	
COUNTY Cass					Surf	Wat	E1.	626.0				1
Boring No. 1					Grnd			600.5				
Boring No. 1 sta 1047+39 SW WW O/S 34 Ft Lt	E1.	N	Qu t/sf	₩ %	At _	24	Hrs	624.0	El.	N	Qu t/sf	₩ %
Ground Surface 631.	5 0		1	1							1	
Grey & Brown, Moist SILTY CLAY	_				Grey SILT	CL	YΥ	Till				
										0		
	_								-25	1 2	0.6 B	25
					Chart	W.		606.	0_			
		3-	0.9	25	Grey	LOAL	ist IT:	111		2		
_	- 5	4_	B						-	5 8	3.7 B	12
		1										
		<u>1</u> -	0.4	32					_	3_		
623.	5 —	2_	B		-			_	-30	14	6.6 B	10
Grey & Brn, V. Moist SILT LOAM	_	1							-			
oudi dom.	-10		0.2	30						7_ 16	8.7	9
· -	-10		P						_	_24_	B	9
		1										
Moist	_	_1_	0.8 B	32						6_ 15	9.3	9
618.	5							_	-35	_22_	_S_14	
Grey, Moist SILTY CLAY LOAM	_	1										
	-15	1 2	0.7 B	31					-			
616. Black, Moist	0								_			
SILTY CLAY	_	1_										
slight organic		1 2	0.7 B	49						-15 -15	8.9	10
613.	o—							_	-40	_20_	В	
Grey, Moist SILTY CLAY Till		0_	0.5	30								
OTHI CHAI IIII	-20	1_	B									
	_								_			
		_°-	0.5	27					_	5		
		1	В	21	Bori	·~ ·		+04		12-	5.5	13







Notes:

- 1. All erosion control items to be furnished and maintained by the Contractor for the entire duration of the project, as directed by the Engineer.
- 2. Unless otherwise indicated, all vegetative and structural erosion and sediment control practices shall be constructed according to minimum standards and specifications in the Illinois Urban Manual and the January 2012 IDOT Standard Specifications.
- 3. A copy of the approved Erosion and Sediment Control Plan shall be maintained on the site at all times.
- 4. Prior to commencing land-disturbing activities in areas other than indicated on these plans (including, but not limited to, additional phases of development and off site borrow or waste areas) a Supplementary Erosion Control Plan shall be submitted to the owner for review.
- 5. The Contractor is responsible for installation of any additional erosion control measures necessary to prevent erosion and sedimentation as determined by the Engineer.
- 6. During any dewatering operations, water will be pumped into sediment basins or silt traps. Dewatering directly into field tiles or storm water structures is prohibited.
- 7. All adjacent streets must be kept clear of debris, inspected daily and cleaned when necessary.
- 8. All erosion control measures must be inspected weekly and after each 1/2" rain event.
- 9. Mulch shall be installed on all slopes and in critical areas immediatly upon final grading.
- 10. The priority shall be given to the completion and stabilization of the disturbed areas. Work in these areas shall not be prolonged in attempt that all final grading and stabilization can take place at one time.
- 11. Stockpiles of soil and other materials to remain in place more than three (3) days shall be furnished with erosion and sediment control measures (I.E. perimeter erosion barrier). Stockpiles to remain in place for 21 days or more shall receive temporary seeding.
- 12. In areas where work is complete, permanent stabilization shall occur within 7 days of completion, and in areas where work has temporarily ceased for 21 days or more, temporary stabilization shall occur by the 14th day after work has ceased.
- 13. Completed slopes shall be seeded and mulched as the excavation proceeds to the extent cosidered desirable and practical. Permanent seeding shall be used whenever possible. Under no circumstances shall the contractor prolong final grading and shaping so that the entire project can be permanently seeded at one time.
- 14. The condition of the construction site for winter shutdown shall be addressed early in the fall growing season so that slopes and other bare earth areas may be stabilized with temporary and/or permanent vegetative cover for proper erosion and sediment control. All open areas that are to remain idle throughout the winter shall receive temporary erosion control measures including temporary seeding, mulching and/or erosion control blanket prior to the end of the fall growing season. The areas to be worked beyond the end of the growing season must incorporate soil stabilization measures that do not rely on vegetative cover such as erosion control blanket and heavy mulching.
- 15. No work shall be performed in flowing water, work in and near the critical areas should be isolated from concentratred flows or stream flow. The stream banks should be stabilized at the end of each day. Once work in this area begins, priority shall be given to the completion of the work and final stabilization of all disturbed areas.

CONTRACTOR CERTIFICATION

"I certify under penalty of law that I understand the terms and conditions of the General National Pollutant Discharge Elimination System (NPDES) Permit (ILRIO) that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this Certification.

GENERAL CONTRACTOR				
Signature	Title			
Company	Date			
SUB-CONTRACTOR Respons	sible for:			
Signature	Title			
Company	Date			
WITNESSED BY OWNER				
Signature	Title			
Company	Date			

INSPECTION AND MAINTENANCE SCHEDULE

ACTIVITY	RESPONSIBLE PARTY	DURATION
Stabilization during construction maintenance	Contractor	Weekly and after every 1/2" of rainfall
Stabilization during construction-observation	Engineer	Weekly and after every 1/2" of rainfall
Vegetation maintenance	Contractor	Completion of Contract
Vegetation and stabilization maintenance	Village of Ashland	Ongoing after construction completion

rProjImpl\Projects\ASHLAND1\Plan Sheets\sheet 20A.dgn

