

CODE NUMBER	PAY ITEM	UNIT	100% STATE TOTAL QUANTITY	5-01	5-02	5-03	5-04	5-05	5-06	5-07	5-08	5-09
				5S010 I074 R180.40	5S010 I074 R181.19	5C010 I074 R181.72	5S010 I074 R182.43	5C010 I074 R183.00	5C010 I074 L183.13	5S010 I074 L182.76	5S010 I074 L181.53	5S010 I074 L180.76
	General Location:			CHAMPAIGN - I-74 EB					CHAMPAIGN - I-74 WB			
	Scope of Work:			SS	SS	GM	SS	GM	GM	SS	SS	SS
63200310	GUARDRAIL REMOVAL	FOOT	229.00	-	-	-	-	-	229.00	-	-	-
67100100	MOBILIZATION	L SUM	1.00	0.13	0.13	0.07	0.13	0.07	0.08	0.13	0.13	0.13
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	10.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	2.00	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	14.00	1.00	2.00	1.00	2.00	1.00	1.00	2.00	2.00	2.00
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.00	0.11	0.11	0.11	0.12	0.11	0.11	0.11	0.11	0.11
72000300	SIGN PANEL - TYPE 3	SOFT	2380.25	232.00	276.25	168.75	474.25	-	168.75	259.75	292.75	507.75
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	2161.50	207.00	237.25	180.00	415.50	-	180.00	251.00	220.25	470.50
72400730	RELOCATE SIGN PANEL - TYPE 3	SOFT	107.25	-	-	-	-	107.25	-	-	-	-
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	5227.00	-	-	2071.00	-	1066.00	2090.00	-	-	-
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' -0" X 4' -6")	FOOT	504.00	84.00	77.00	-	91.00	-	-	85.00	84.00	83.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	290.00	48.50	39.50	-	58.00	-	-	44.00	50.00	50.00
73400100	CONCRETE FOUNDATIONS	CUYD	10.90	-	-	4.18	-	2.54	4.18	-	-	-
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	6.00	1.00	1.00	-	1.00	-	-	1.00	1.00	1.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3.00	-	-	1.00	-	1.00	1.00	-	-	-
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	3.00	-	-	1.00	-	1.00	1.00	-	-	-
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	26.00	**	**	**	**	**	**	**	**	**
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	24.00	4.00	4.00	-	4.00	-	-	4.00	4.00	4.00
X7350005	SIGN SUPPORT REPAIR	EACH	1.00	-	-	-	-	-	-	-	1.00	-
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	9.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.00	0.11	0.11	0.11	0.12	0.11	0.11	0.11	0.11	0.11

** 7 days advance notice for I-74 EB simple span erection + 7 days I-74 WB + 3 days advance notice for I-74 EB ground mount drilled shaft foundations + 3 days I-74 WB + 3 days advance notice for I-74 EB cantilever removal and ground mount erection + 3 days I-74 WB = 26 CAL DA for CHANGEABLE MESSAGE SIGN

SS = Overhead Sign Structure Replacement w/ Simple Span - (Re-using Foundations)
GM = Cantilever Sign Structure Replacement w/ Breakaway Ground Mount

* 0-5 OVD SIN STR REPL 2013-09

FILE NAME *	USER NAME = buckleejj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.				
c:\pwork\pvidot\buclleejj\d0380231\054	222-Sht-Schedule.dgn	DRAWN -	REVISED -						74	*	Champaign	50	6				
#MODELNAME	PLOT SCALE = 40,0000' / in.	CHECKED -	REVISED -						SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 46222	
	PLOT DATE = 8/22/2012	DATE -	REVISED -						[ILLINOIS] FED. AID PROJECT								