

Location No.	5-01			
Structure No.	5 S 010 I074 R180.40			
County / Route	CHAMPAIGN CO. - I-74 EB - Just West of Prospect Ave.			
Scope of Work	This overhead sign structure is being replaced on existing foundations.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SOFT	232.00	
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	207.00	
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	84.00	
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	48.50	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00	
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	

Note: new end supports are included in the cost of the OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs.
Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

Location No.	5-02			
Structure No.	5 S 010 I074 R181.19			
County / Route	CHAMPAIGN CO. - I-74 EB - Just West of Nell St.			
Scope of Work	This overhead sign structure is being replaced on existing foundations.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00	
72000300	SIGN PANEL - TYPE 3	SOFT	276.25	
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	237.25	
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	77.00	
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	39.50	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00	
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	

Note: new end supports are included in the cost of the OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs.
Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

• D-5 OVD SIGN STR REPL 2013-09

FILE NAME *	USER NAME * buckleejj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES INDIVIDUAL TRUSS LOCATIONS				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\dot\buckleejj\d0388231\054622-Sht-Schedule.dgn		DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	74	Champaign	50	7
#MODELNAME*	PLOT SCALE * 40.0000 ' / in.	CHECKED -	REVISED -								CONTRACT NO. 46222			
	PLOT DATE * 8/22/2012	DATE -	REVISED -						ILLINOIS FED. AID PROJECT					