

Location No.	5-03		
Structure No.	5 C 010 1074 R181.72		
County / Route	CHAMPAIGN CO. - I-74 EB - between Neil St. and Lincoln Ave.		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SOFT	168.75
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	180.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2071.00
73400100	CONCRETE FOUNDATIONS	CUYD	4.18
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Pay Item for CMS is for the advanced Interstate notice only. CMS shown on Standards are included in the cost of the Standard.

Location No.	5-04		
Structure No.	5 S 010 1074 R182.43		
County / Route	CHAMPAIGN CO. - I-74 EB - just West of Lincoln Ave.		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SOFT	474.25
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	415.50
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' -0" X 4' -6")	FOOT	91.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	58.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Note: new end supports are included in the cost of the OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs.  
Pay Item for CMS is for the advanced Interstate notice only. CMS shown on Standards are included in the cost of the Standard.

• 0-5 OVD SIGN STR REPL 2013-09

FILE NAME *	USER NAME * buchiesjj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES INDIVIDUAL TRUSS LOCATIONS</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pvidat\buchiesjj\0308231\05	222-Sht-Schedule.dgn	DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	74	Champaign	50	8
#MODELNAME*	PLOT SCALE * 10.0000 * / in.	CHECKED -	REVISED -								CONTRACT NO. 46222			
	PLOT DATE * 8/22/2012	DATE -	REVISED -								(ILLINOIS) FED. AID PROJECT			