

Location No.	5-05		
Structure No.	5 C 010 I074 R183.00		
County / Route	CHAMPAIGN CO. - I-74 EB - between Lincoln Ave. and US Route 45.		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72400730	RELOCATE SIGN PANEL - TYPE 3	SOFT	107.25
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1066.00
73400100	CONCRETE FOUNDATIONS	CUYD	2.54
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Existing sign is to be reused and reinstalled as a breakaway ground mount.
Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

Location No.	5-06		
Structure No.	5 C 010 I074 L183.13		
County / Route	CHAMPAIGN CO. - I-74 WB - between US Route 45 and Lincoln Ave.		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
63200310	GUARDRAIL REMOVAL	FOOT	229.00
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SOFT	168.75
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	180.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2090.00
73400100	CONCRETE FOUNDATIONS	CUYD	4.18
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

* 0-5 OVD SIGN STR REPL 2013-09

FILE NAME *	USER NAME = bucklesjj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES INDIVIDUAL TRUSS LOCATIONS				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pe_work\pedit\bucksjj\0308231\054	222-Sht-Schedule.dgn	DRAWN -	REVISED -		74		Champaign	50	9				
#MODELNAME#	PLOT SCALE = 40,0000' / in.	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 46222		
	PLOT DATE = 8/22/2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								