

Location No.	5-07		
Structure No.	5 S 010 I074 L182.76		
County / Route	CHAMPAIGN CO. - I-74 WB - just East of Lincoln Ave.		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SOFT	259.75
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	251.00
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	85.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	44.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Note: new end supports are included in the cost of the OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs.
Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

Location No.	5-08		
Structure No.	5 S 010 I074 L181.53		
County / Route	CHAMPAIGN CO. - I-74 WB - just East of Neil St.		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	2.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SOFT	292.75
72400330	REMOVE SIGN PANEL - TYPE 3	SOFT	220.25
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	84.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	50.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X7350005	SIGN SUPPORT REPAIR	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Note: new end supports are included in the cost of the OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs.
Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.
An additional set-up of 701401 to close the WBPL will be paid for to address the pay item SIGN SUPPORT REPAIR. See Spec. Prov.

• D-5 OVD SIGN STR REPL 2013-09

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES INDIVIDUAL TRUSS LOCATIONS			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\dot\buckles\j\0308231\054222-Sht-Schedule.dgn	bucklesj	DRAWN -	REVISED -					74		Champaign	50	10
PLOT SCALE * 10.0000 ' / in.		CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 46222				
#MODELNAME*		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							