

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED. 10% STATE 10% VILLAGE | 80% FED. 15% STATE 5% VILLAGE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOSEL, 01	LOSEL, 01		LOSEL, 01	LOSEL, 02	LOSEL, 03
				ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	836	70	766				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	140		140				
20101100	TREE TRUNK PROTECTION	EACH	14	14					
20101700	SUPPLEMENTAL WATERING	UNIT	8		8				
20200100	EARTH EXCAVATION	CU YD	162,409	61,483	100,926				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	18,535	12,897	5,638				
20800150	TRENCH BACKFILL	CU YD	4,916	4,622	294				
20900110	POROUS GRANULAR BACKFILL	CU YD	2,365				2,365		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	130,713	121,423	9,290				
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,871	1,871					
21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	64,486	36,386	28,100				
21101685	TOPSOIL FURNISH AND PLACE, 24"	SO YD	7,497	7,497					
25000210	SEEDING, CLASS 2A	ACRE	9.5	9.1	0.4				
25000310	SEEDING, CLASS 4	ACRE	5.4		5.4				

* SPECIALITY ITEM

S00-1



USER NAME * teupercheck	DESIGNED	REVISED
PLOT SCALE * 1:1	DRAWN	REVISED -
PLOT DATE * 22-OCT-2012	CHECKED	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	6
CONTRACT NO. 60637			ILLINOIS FED. AID PROJECT	