

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED. 80% FED.
10% STATE 15% STATE
10% VILLAGE 5% VILLAGE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				TS-MONTROSE	TS-LAWRENCE
				ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,341	816	525				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,341	816	525				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,341	816	525				
25100630	EROSION CONTROL BLANKET	SQ YD	70,097	41,997	28,100				
25100900	TURF REINFORCEMENT MAT	SQ YD	3,772	3,772					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,489	907	582				
28000305	TEMPORARY DITCH CHECKS	FOOT	391	83	308				
28000400	PERIMETER EROSION BARRIER	FOOT	14,011	11,611	2,400				
28000500	INLET AND PIPE PROTECTION	EACH	16		16				
28000510	INLET FILTERS	EACH	163	163					
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	70,097	41,997	28,100				
28100105	STONE RIPRAP, CLASS A3	SQ YD	23		23				
28200200	FILTER FABRIC	SQ YD	23		23				
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	5,259	5059	200				

* SPECIALITY ITEM

S00-2



USER NAME = leupen@hntb	DESIGNED	REVISED -
PLOT SCALE = 1/4"	DRAWN	REVISED -
PLOT DATE = 22-OCT-2012	CHECKED	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	7
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60637	