

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED. 10% STATE 10% VILLAGE | 80% FED. 15% STATE 5% VILLAGE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,240.7			1,240.7				
50300260	BRIDGE DECK GROOVING	SQ YD	2,688			2,688				
50300285	FORM LINER TEXTURED SURFACE	SQ FT	7,774			7,774				
50300300	PROTECTIVE COAT	SQ YD	10,224		7,135	3,089				
50500305	ERECTING STRUCTURAL STEEL	L SUM	1			1				
50500505	STUD SHEAR CONNECTORS	EACH	10,465			10,465				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	497,680			497,680				
50800515	BAR SPLICERS	EACH	719			719				
51100100	SLOPE WALL 4 INCH	SQ YD	1,670			1,670				
51500100	NAME PLATES	EACH	2			2				
52000030	PREFORMED JOINT SEAL 2 1/2"	FOOT	126			126				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	368			368				
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20			20				
52100520	ANCHOR BOLTS, 1"	EACH	40			40				

* SPECIALITY ITEM

S00-5



USER NAME: lspanolchek	DESIGNED	REVISED -
PLOT SCALE: 1"=10'	DRAWN	REVISED -
PLOT DATE: 22-OCT-2012	CHECKED	REVISED -
	DATE: 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 0105 WRS&HB	COUNTY COOK	TOTAL SHEETS 605	SHEET NO. 10
CONTRACT NO. 60637			ILLINOIS FED. AID PROJECT	