

80% FED. / 20% STATE

80% FED. 10% STATE 15% STATE
10% VILLAGE 5% VILLAGE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY	BALMORAL	BRIDGE	LIGHTING	TS-MONTROSE	TS-LAWRENCE	
				0003 URBAN	0003 URBAN	0008 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	
60204505	CATCH BASINS, TYPE A, 5' DIAMETER, TYPE B GRATE	EACH	1		1					
60218400	MANHOLES, TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID	EACH	8	4	4					
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	29	29						
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2						
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	17	14	3					
60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2					
60247160	DRAINAGE STRUCTURES, TYPE 1 WITH TWO TYPE 20 FRAMES AND GRATES	EACH	13	13						
60247170	DRAINAGE STRUCTURES, TYPE 2 WITH TWO TYPE 22 FRAMES AND GRATES	EACH	1	1						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1		1					
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2						
60260100	INLETS TO BE ADJUSTED	EACH	1	1						
60500040	REMOVING MANHOLES	EACH	56	55	1					
60500050	REMOVING CATCH BASINS	EACH	18	17	1					

14 * SPECIALITY ITEM

S00-9



USER NAME * Isupaneback	DESIGNED	REVISED -
PLOT SCALE = 1/1	DRAWN	REVISED -
PLOT DATE * 22-OCT-2012	CHECKED	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	14
CONTRACT NO. 60637			ILLINOIS FED. AID PROJECT	