

80% FED. / 20% STATE

80% FED. 80% FED.
10% STATE 15% STATE
10% VILLAGE 5% VILLAGE

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BALMORAL	BRIDGE	LIGHTING	TS-MONTROSE	TS-LAWRENCE
				0003 URBAN	0003 URBAN	0008 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
81400100	HANDHOLE	EACH	23	15				4	4
81400200	HEAVY-DUTY HANDHOLE	EACH	6	2				2	2
81400300	DOUBLE HANDHOLE	EACH	4					2	2
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	2		2				
81603081	UNIT DUCT, 600V, 3-1/C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE) 1 1/2" DIA. POLYETHYLENE	FOOT	19,526				19,526		
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1,600		1,600				
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	20,274	474	19,800				
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	5,988	1,488	4,500				
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	3,900		3,900				
81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	495				495		
81702180	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	150				150		
81702200	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE UDE) 3-1/C 350MCM	FOOT	149				149		
81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	482	289			193		
81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	26,437				26,437		

* SPECIALITY ITEM

S00-17



USER NAME : Isupanchek	DESIGNED	REVISED -
	DRAWN	REVISED -
PLOT SCALE : 1:1	CHECKED	REVISED -
PLOT DATE : 22-OCT-2012	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	22
CONTRACT NO. 60637			ILLINOIS FED. AID PROJECT	