

SUMMARY OF QUANTITIES

80% FED./20% STATE

80% FED. 80% FED.
10% STATE 15% STATE
10% VILLAGE 5% VILLAGE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	52				52		
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	161				161		
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	28				28		
82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	7		7				
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	143				143		
82107700	UNDERPASS LUMINAIRE, 400 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	27		27				
82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240 VOLT, 100 AMP	EACH	1		1				
83001250	LIGHT POLE, ALUMINUM, 35 FT. M.H., 6 FT. DAVIT ARM - TWIN	EACH	1				1		
83002600	LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. DAVIT ARM	EACH	10				10		
83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	62				62		
83050915	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-6 FT. DAVIT ARMS	EACH	9				9		
83057295	LIGHT POLE, WOOD, 50 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	102				102		
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	1,260				1,260		
83600352	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8 5/8" X 6'	EACH	18		18				

* SPECIALITY ITEM

S00-18



USER NAME * jspencheck	DESIGNED	REVISED -
PLOT SCALE = 1/4"	DRAWN	REVISED -
PLOT DATE * 22-OCT-2012	CHECKED	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	23
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60637	