

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED.	80% FED.
10% STATE	15% STATE
10% VILLAGE	5% VILLAGE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BALMORAL	BRIDGE	LIGHTING	TS-MONTROSE	TS-LAWRENCE
				0003 URBAN	0003 URBAN	0008 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1435					939	496
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7,969					4,285	3,684
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	75					32	43
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	2,725					1,444	1,281
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2					1	1
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2					1	1
87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	1						1
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	2					2	
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1						1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1					1	
87703020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 58 FT.	EACH	2					1	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24					12	12
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8					4	4
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10						10

* SPECIALITY ITEM

S00-20



USER NAME = lsupencheck	DESIGNED	REVISED -
PLOT SCALE = 1/4"	DRAWN	REVISED -
PLOT DATE = 22-OCT-2012	CHECKED	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 0105 WRS&HB	COUNTY COOK	TOTAL SHEETS 605	SHEET NO. 25
CONTRACT NO. 60G37				
ILLINOIS FED. AID PROJECT				