

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED.	80% FED.
10% STATE	15% STATE
10% VILLAGE	5% VILLAGE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN	TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN
• 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2					1	1
<i>89501400</i>	<i>RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT</i>	<i>EACH</i>	<i>6</i>					<i>3</i>	<i>3</i>
• 89502200	MODIFY EXISTING CONTROLLER	EACH	1	1					
<i>89501410</i>	<i>RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT</i>	<i>EACH</i>	<i>2</i>					<i>1</i>	<i>1</i>
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1	1					
• 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1010	1010					
• 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2					1	1
• 89502380	REMOVE EXISTING HANDHOLE	EACH	38	7	4		10	9	8
• 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	20					10	10
X0321809	PERMANENT GROUND ANCHOR	EACH	50			50			
X0322916	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	EACH	6	6					
X0323260	SEDIMENT BASIN	EACH	1	1					
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	2	2					
<i>X0324085</i>	<i>EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C</i>	<i>FOOT</i>	<i>1954</i>					<i>1006</i>	<i>948</i>
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	7,820			7,820			
X0324807	CLOSED CIRCUIT TELEVISION CABINET EQUIPMENT	EACH	2	2					
• X0324915	RELOCATE LIGHTING UNITS AND POLES	EACH	4				4		

* SPECIALITY ITEM

S00-22



USER NAME • lsopenback	DESIGNED	REVISED -
PLOT SCALE • 1/4"	DRAWN	REVISED -
PLOT DATE • 22-OCT-2012	CHECKED	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRSAB	COOK	605	27
CONTRACT NO. 60637			ILLINOIS FED. AID PROJECT	