

SUMMARY OF QUANTITIES

80% FED. / 20% STATE
 80% FED. 10% STATE 10% VILLAGE
 80% FED. 15% STATE 5% VILLAGE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				TS-MONTROSE 0021 URBAN	TS-LAWRENCE 0021 URBAN
				ROADWAY 0003 URBAN	BALMORAL 0003 URBAN	BRIDGE 0008 URBAN	LIGHTING 0021 URBAN		
• Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	2	2					
• Z0033052	COMMUNICATIONS VAULT	EACH	4	4					
Z0046306	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	1,477			1,477			
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	74	74					
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	20	20					
Z0056626	STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	40	40					
Z0062456	TEMPORARY PAVEMENT	SQ YD	41,660	41,660					
Z0062458	TEMPORARY PAVEMENT (VARIABLE DEPTH)	TON	690	690					
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	4,020			4,020			
• Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2				1	1	
X4201050	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10 3/4 (JOINTED)	SQ YD	275	275					
• X8301051	MAST ARM, ALUMINUM, 20 FT.	EACH	52			52			
• X8300415	LIGHT POLE, STAINLESS STEEL, 15 FT. M.H.	EACH	15			15			
• X8300420	LIGHT POLE, STAINLESS STEEL, 17.5 FT. M.H.	EACH	56			56			

• SPECIALITY ITEM

S00-28



USER NAME	DESIGNED	REVISED
• lsupencheck		-
DRAWN	CHECKED	REVISED
MMK	LLS	-
DATE	DATE	REVISED
10/19/12		-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 28 OF 28 SHEETS STA. TO STA.

F.A.P. FTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	33
CONTRACT NO. 60637			ILLINOIS FED. AID PROJECT	