

EARTHWORK SCHEDULE - MANNHEIM ROAD

BEGIN STATION	END STATION	EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE* (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	AGGREGATE SUBGRADE IMPROVEMENT (CU YD)	TOPSOIL (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)
28+00.00	28+50.00	105	0	79	2	77	0	16	14
28+50.00	29+00.00	93	0	70	3	67	0	26	17
29+00.00	29+50.00	100	0	75	4	71	0	31	16
29+50.00	30+00.00	110	0	83	6	77	0	35	14
30+00.00	30+50.00	113	0	85	25	60	0	43	24
30+50.00	31+00.00	117	0	88	38	50	0	51	33
31+00.00	31+50.00	126	0	95	34	61	0	54	32
31+50.00	32+00.00	123	0	92	26	66	0	50	28
32+00.00	32+50.00	124	0	93	15	78	0	40	20
32+50.00	33+00.00	517	0	388	22	366	0	56	41
33+00.00	33+50.00	916	0	687	27	660	0	79	66
33+50.00	34+00.00	926	0	695	22	673	0	81	65
34+00.00	34+50.00	922	0	692	17	675	0	87	65
34+50.00	35+00.00	937	0	703	15	688	0	87	66
35+00.00	35+50.00	674	0	506	16	490	0	65	41
35+50.00	36+00.00	393	0	295	15	280	0	44	16
36+00.00	36+50.00	387	0	290	19	271	0	36	16
36+50.00	37+00.00	370	0	278	22	256	0	31	16
37+00.00	37+50.00	353	0	265	20	245	0	33	16
37+50.00	38+00.00	365	0	274	13	261	0	33	16
38+00.00	38+50.00	386	0	290	6	284	0	28	16
38+50.00	39+00.00	397	0	298	4	294	0	28	15
39+00.00	39+50.00	415	0	311	2	309	0	28	15
39+50.00	40+00.00	410	0	308	4	304	0	17	15
40+00.00	40+50.00	400	0	300	5	295	0	8	14
40+50.00	41+00.00	412	0	309	1	308	0	8	14
41+00.00	41+50.00	428	0	321	0	321	0	8	14
41+50.00	42+00.00	425	0	319	1	318	0	10	15
42+00.00	42+50.00	397	0	298	4	294	0	12	16
42+50.00	43+00.00	368	0	276	10	266	0	13	17
43+00.00	43+50.00	332	0	249	14	235	0	13	17
43+50.00	44+00.00	291	0	218	17	201	0	13	18
44+00.00	44+50.00	212	0	159	24	135	0	12	19
44+50.00	45+50.00	428	0	321	47	274	0	26	36
45+50.00	46+00.00	286	0	215	20	195	0	16	16
46+00.00	46+50.00	301	0	226	21	205	0	17	16
46+50.00	47+00.00	304	0	228	19	209	0	16	16
47+00.00	47+50.00	305	0	229	16	213	0	15	15
47+50.00	48+00.00	300	0	225	16	209	0	15	15
48+00.00	48+50.00	147	250	110	34	76	110	15	37
48+50.00	49+00.00	1	497	1	47	-46	218	15	43
49+00.00	49+50.00	1	497	1	41	-40	217	14	28
49+50.00	50+00.00	2	502	2	37	-36	216	17	29
50+00.00	50+50.00	4	507	3	35	-32	214	19	30
50+50.00	51+00.00	6	509	5	33	-29	214	18	29
51+00.00	51+50.00	5	504	4	33	-29	214	16	28
51+50.00	52+00.00	145	249	109	23	86	107	16	14
52+00.00	52+50.00	290	0	218	11	207	0	16	0
52+50.00	53+00.00	293	0	220	13	207	0	14	0
53+00.00	53+50.00	291	0	218	15	203	0	13	0
53+50.00	54+00.00	287	0	215	19	196	0	13	0
54+00.00	54+50.00	282	0	212	22	190	0	11	0
54+50.00	55+00.00	282	0	212	24	188	0	10	0
55+00.00	55+50.00	281	0	211	20	191	0	13	0
55+50.00	56+00.00	282	0	212	13	199	0	16	0
56+00.00	56+50.00	288	0	216	8	208	0	19	0
56+50.00	57+00.00	296	0	222	6	216	0	25	0
57+00.00	57+50.00	310	0	233	4	229	0	20	0
57+50.00	58+00.00	322	0	242	7	235	0	10	0
58+00.00	58+50.00	330	0	248	14	234	0	8	0
58+50.00	59+00.00	321	0	241	18	223	0	8	0
59+00.00	59+50.00	308	0	231	18	213	0	7	0
59+50.00	60+00.00	302	0	227	16	211	0	8	0
60+00.00	61+00.00	588	0	441	17	424	0	14	0
61+00.00	61+50.00	308	0	231	0	231	0	16	0
61+50.00	62+00.00	355	0	266	0	266	0	27	0
62+00.00	62+50.00	381	0	286	6	280	0	30	0
62+50.00	63+00.00	356	0	267	9	258	0	30	0
63+00.00	63+50.00	347	0	260	6	254	0	31	0
63+50.00	64+00.00	398	0	299	9	290	0	38	0
64+00.00	64+50.00	465	0	349	10	339	0	45	0
64+50.00	65+00.00	514	0	386	13	373	0	48	0
65+00.00	65+50.00	532	0	399	17	382	0	47	0

SC-02



USER NAME = lsupencheck	DESIGNED	REVISED -
PLOT SCALE = 1:1	DRAWN MMK	REVISED -
PLOT DATE = 22-OCT-2012	CHECKED LLS	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 6 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	48
				CONTRACT NO. 60G37
ILLINOIS FED. AID PROJECT				