

EARTHWORK SCHEDULE - MANNHEIM ROAD

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
65+50.00	66+00.00	483	0	362	17	345	0	40	0
66+00.00	66+50.00	431	0	323	14	309	0	34	0
66+50.00	67+00.00	424	0	318	21	297	0	34	0
67+00.00	67+50.00	439	0	329	18	311	0	34	0
67+50.00	68+00.00	472	0	354	7	347	0	35	0
68+00.00	68+50.00	468	0	351	8	343	0	38	0
68+50.00	69+00.00	466	0	350	13	337	0	41	0
69+00.00	69+50.00	506	0	380	16	364	0	44	0
69+50.00	70+00.00	517	0	388	36	352	0	47	0
70+00.00	70+50.00	549	0	412	42	370	0	47	0
70+50.00	71+00.00	571	0	428	33	395	0	47	0
71+00.00	71+50.00	530	0	398	38	360	0	48	0
71+50.00	72+00.00	495	0	371	42	329	0	49	0
72+00.00	72+50.00	490	0	368	39	329	0	49	0
72+50.00	73+00.00	499	0	374	34	340	0	48	0
73+00.00	73+50.00	496	0	372	35	337	0	48	0
73+50.00	74+00.00	400	0	300	43	257	0	27	0
74+00.00	74+50.00	157	0	118	26	92	0	3	0
74+50.00	75+00.00	0	0	0	0	0	0	0	0
75+00.00	75+50.00	0	0	0	0	0	0	0	0
75+50.00	76+00.00	0	243	0	52	-52	111	12	5
76+00.00	76+50.00	1	486	1	100	-99	221	24	11
76+50.00	77+00.00	4	484	3	73	-70	221	24	13
77+00.00	77+50.00	8	482	6	51	-45	221	24	14
77+50.00	78+00.00	8	482	6	51	-45	221	24	15
78+00.00	78+50.00	8	482	6	51	-45	221	24	15
78+50.00	79+00.00	8	482	6	51	-45	221	24	15
79+00.00	79+50.00	204	241	153	32	121	110	19	7
79+50.00	80+00.00	338	0	254	14	240	0	14	0
80+00.00	80+50.00	273	0	205	18	187	0	14	0
80+50.00	81+00.00	265	0	199	18	181	0	14	0
81+00.00	81+50.00	262	0	197	17	180	0	15	0
81+50.00	82+00.00	245	0	184	22	162	0	15	0
82+00.00	82+50.00	200	0	150	26	124	0	15	0
82+50.00	83+00.00	243	0	182	27	155	0	16	0
83+00.00	83+50.00	285	0	214	25	189	0	16	0
83+50.00	84+00.00	254	0	191	22	169	0	15	0
84+00.00	84+50.00	254	0	191	20	171	0	14	0
84+50.00	85+00.00	301	0	226	10	216	0	18	0
85+00.00	85+50.00	356	0	267	1	266	0	21	0
85+50.00	86+00.00	377	0	283	2	281	0	23	0
86+00.00	86+50.00	424	0	318	2	316	0	28	0
86+50.00	87+00.00	477	0	358	0	358	0	32	0
87+00.00	87+50.00	514	0	386	6	380	0	35	0
87+50.00	88+00.00	536	0	402	13	389	0	38	0
88+00.00	89+00.00	1,075	0	806	27	779	0	76	0
89+00.00	89+50.00	538	0	404	8	396	0	37	0
89+50.00	90+00.00	536	0	402	7	395	0	38	0
90+00.00	90+50.00	525	0	394	7	387	0	38	0
90+50.00	91+00.00	505	0	379	7	372	0	38	0
91+00.00	91+50.00	271	292	203	13	190	85	35	9
91+50.00	92+00.00	48	587	36	20	16	172	33	19
92+00.00	92+50.00	22	596	17	23	-7	171	24	19
92+50.00	93+00.00	0	598	0	26	-26	169	15	20
93+00.00	93+50.00	0	605	0	26	-26	172	16	21
93+50.00	94+00.00	0	624	0	26	-26	175	17	23
94+00.00	94+50.00	0	570	0	22	-22	158	15	23
94+50.00	95+00.00	171	254	128	11	117	71	12	11
95+00.00	95+50.00	365	0	274	3	271	0	12	0
95+50.00	96+00.00	400	0	300	0	300	0	9	0
96+00.00	96+50.00	408	0	306	0	306	0	5	0
96+50.00	97+00.00	408	0	306	2	304	0	7	0
97+00.00	97+50.00	418	0	314	4	310	0	8	0
97+50.00	98+00.00	429	0	322	4	318	0	10	0
98+00.00	98+50.00	432	0	324	2	322	0	10	0
98+50.00	99+00.00	436	0	327	0	327	0	8	0
99+00.00	99+50.00	468	0	351	0	351	0	14	0
99+50.00	100+00.00	502	0	377	0	377	0	17	0
100+00.00	100+50.00	510	0	383	2	381	0	22	0
100+50.00	101+00.00	500	0	375	2	373	0	22	0
101+00.00	101+50.00	494	0	371	1	370	0	18	0
101+50.00	102+00.00	502	0	377	1	376	0	22	0
102+00.00	102+50.00	504	0	378	0	378	0	25	0

SC-03



USER NAME = lsupencheck  
 PLOT SCALE = 1:1  
 PLOT DATE = 22-OCT-2012

DESIGNED  
 DRAWN  
 CHECKED  
 DATE 10/19/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 6 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	606	279
CONTRACT NO. 60G37			ILLINOIS FED. AID PROJECT	