

EARTHWORK SCHEDULE - MANNHEIM ROAD									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
102+50.00	103+00.00	510	0	383	1	382	0	29	0
103+00.00	103+50.00	528	0	396	4	392	0	35	0
103+50.00	104+00.00	551	0	413	7	406	0	38	0
104+00.00	104+50.00	580	0	435	8	427	0	41	0
104+50.00	105+00.00	592	0	444	8	436	0	44	0
105+00.00	105+50.00	597	0	448	8	440	0	46	0
105+50.00	106+00.00	612	0	459	11	448	0	47	0
106+00.00	106+50.00	493	0	370	8	362	0	29	0
106+50.00	107+00.00	364	0	273	3	270	0	10	0
107+00.00	107+50.00	377	0	283	2	281	0	9	0
107+50.00	108+00.00	401	0	301	3	298	0	10	0
108+00.00	108+50.00	411	0	308	4	304	0	12	0
108+50.00	109+00.00	440	0	330	2	328	0	10	0
109+00.00	109+50.00	478	0	359	0	359	0	7	0
109+50.00	110+00.00	486	0	365	0	365	0	6	0
110+00.00	110+50.00	489	0	367	0	367	0	7	0
110+50.00	111+00.00	492	0	369	0	369	0	7	0
111+00.00	111+50.00	470	0	353	1	352	0	7	0
111+50.00	112+00.00	442	0	332	1	331	0	6	0
112+00.00	112+50.00	414	0	311	0	311	0	6	0
112+50.00	113+00.00	380	0	285	0	285	0	7	0
113+00.00	113+50.00	364	0	273	0	273	0	8	0
113+50.00	114+00.00	313	0	235	14	221	0	8	0
<b>MANNHEIM SUB-TOTAL</b>		<b>59,377</b>	<b>11,023</b>	<b>44,533</b>	<b>2,705</b>	<b>41,828</b>	<b>4,230</b>	<b>4,211</b>	<b>1,419</b>

EARTHWORK SCHEDULE - RAMP M2CD1									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
910+25.00	910+50.00	49	0	37	11	26	0	16	16
910+50.00	910+75.00	34	0	26	9	17	0	16	13
910+75.00	911+00.00	33	0	25	7	18	0	12	10
911+00.00	911+25.00	34	0	26	5	21	0	10	7
911+25.00	911+50.00	35	0	26	4	22	0	9	6
911+50.00	911+75.00	36	0	27	3	24	0	7	4
911+75.00	912+00.00	37	0	28	0	28	0	5	3
912+00.00	912+25.00	38	0	29	0	29	0	4	2
912+25.00	912+50.00	40	0	30	0	30	0	3	1
912+50.00	912+75.00	40	0	30	0	30	0	3	1
912+75.00	913+00.00	41	0	31	0	31	0	3	2
913+00.00	913+25.00	43	0	32	0	32	0	3	2
913+25.00	913+50.00	44	0	33	0	33	0	3	3
913+50.00	913+63.41	24	0	18	0	18	0	1	1
<b>SUB-TOTAL</b>		<b>528</b>	<b>0</b>	<b>396</b>	<b>39</b>	<b>357</b>	<b>0</b>	<b>95</b>	<b>71</b>

EARTHWORK SCHEDULE - RAMP EBNE									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
1103+07.23	1103+25.00	37	0	28	4	24	0	10	10
1103+25.00	1103+50.00	55	0	41	5	36	0	13	13
1103+50.00	1103+75.00	57	0	43	1	42	0	5	5
1103+75.00	1104+00.00	58	0	44	3	41	0	5	5
1104+00.00	1104+25.00	57	0	43	5	38	0	7	7
1104+25.00	1104+50.00	55	0	41	4	37	0	6	7
1104+50.00	1104+75.00	52	0	39	3	36	0	6	6
<b>SUB-TOTAL</b>		<b>371</b>	<b>0</b>	<b>278</b>	<b>25</b>	<b>253</b>	<b>0</b>	<b>52</b>	<b>53</b>

EARTHWORK SCHEDULE - RAMP SBEB									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
1001+75.00	1001+75.00	24	0	18	2	16	0	4	4
1002+00.00	1002+00.00	42	0	32	2	30	0	5	5
1002+25.00	1002+25.00	46	0	35	2	33	0	5	5
1002+50.00	1002+50.00	50	0	38	1	37	0	4	4
<b>SUB-TOTAL</b>		<b>162</b>	<b>0</b>	<b>122</b>	<b>7</b>	<b>115</b>	<b>0</b>	<b>18</b>	<b>18</b>

SC-04



USER NAME = lsupencheck  
 PLOT SCALE = 1:1  
 PLOT DATE = 22-OCT-2012

DESIGNED  
 DRAWN MMK  
 CHECKED LLS  
 DATE 10/19/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 4 OF 6 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	50
CONTRACT NO. 60G37				
ILLINOIS FED. AID PROJECT				