

EARTHWORK SCHEDULE - MONTROSE									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
7+10.00	7+25.00	55	0	41	0	41	0	2	2
7+25.00	7+50.00	92	0	69	0	69	0	3	3
7+50.00	7+75.00	96	0	72	0	72	0	3	4
7+75.00	8+00.00	105	0	79	0	79	0	3	5
8+00.00	8+25.00	117	0	88	0	88	0	3	6
8+25.00	8+50.00	129	0	97	0	97	0	3	7
SUB-TOTAL		594	0	446	0	446	0	17	27

EARTHWORK SCHEDULE - LAWRENCE									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
11+40.66	11+50.00	0	51	0	7	-7	26	3	8
11+50.00	11+60.00	0	53	0	8	-8	27	4	9
11+60.00	11+70.00	0	54	0	8	-8	29	4	9
11+70.00	11+90.00	0	130	0	12	-12	74	3	9
11+90.00	12+00.00	0	74	0	3	-3	44	0	0
12+00.00	12+30.00	0	184	0	17	-17	104	6	9
12+30.00	12+50.00	0	103	0	15	-15	48	6	14
12+50.00	12+75.00	1	137	1	14	-13	60	5	18
12+75.00	13+00.00	1	141	1	10	-9	59	4	16
13+00.00	13+25.00	2	142	2	7	-6	60	3	14
13+25.00	13+32.58	1	43	1	1	0	18	0	4
13+32.58	13+50.00	2	101	2	6	-5	40	1	9
13+50.00	14+00.00	6	299	5	21	-17	111	4	25
14+00.00	14+25.00	4	149	3	10	-7	53	3	12
14+25.00	14+50.00	4	143	3	10	-7	51	4	12
14+50.00	14+75.00	14	70	11	5	6	25	4	11
14+75.00	15+00.00	21	0	16	0	16	0	5	11
SUB-TOTAL		56	1,874	42	154	-112	829	59	190

EARTHWORK SCHEDULE - RAMP A									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
18+75.00	19+00.00	18	0	14	9	5	0	0	10
19+00.00	19+25.00	27	0	20	6	14	0	0	11
19+25.00	19+50.00	33	0	25	4	21	0	0	12
19+50.00	19+75.00	36	0	27	3	24	0	0	12
19+75.00	20+00.00	37	0	28	2	26	0	0	8
20+00.00	20+25.00	38	0	29	1	28	0	0	5
20+25.00	20+50.00	38	0	29	1	28	0	0	5
20+50.00	20+75.00	38	0	29	1	28	0	0	3
20+75.00	21+00.00	39	0	29	0	29	0	0	4
SUB-TOTAL		304	0	228	27	201	0	0	70

EARTHWORK SCHEDULE - RAMP B									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
1203+15.36	1203+18.61	5	0	4	0	4	0	1	1
1203+18.61	1203+25.00	10	0	8	1	7	0	2	3
1203+25.00	1203+40.00	23	0	17	3	14	0	8	8
1203+40.00	1203+50.00	15	0	11	2	9	0	5	5
1203+50.00	1203+58.07	12	0	9	0	9	0	2	2
1203+58.07	1203+75.00	26	0	20	1	19	0	4	4
SUB-TOTAL		91	0	68	7	61	0	22	23

SC-05



USER NAME = lsupencheck
 PLOT SCALE = 1:1
 PLOT DATE = 22-OCT-2012

DESIGNED
 DRAWN MMK
 CHECKED LLS
 DATE 10/19/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 5 OF 6 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	51
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60G37	