

DRAINAGE STRUCTURE DATA

STRUCTURE NO.	DESCRIPTION	STATION	OFFSET	DIR.	PROPOSED RIM ELEV.	NORTH	SOUTH	EAST	WEST	PIPE ID-PIPE SIZE NORTH	PIPE ID-PIPE SIZE SOUTH	PIPE ID-PIPE SIZE EAST	PIPE ID-PIPE SIZE WEST	IDOT SHEET NO.	NOTES:
073	5' DIA MH TY A	T1F, CL	59+26.90	3.5	R	644.26		639.66	639.66		68 - DIA24"	71 - DIA 12"	70 - DIA 12"	DR-03	
074	4' DIA CB TY A	T24	59+26.90	15.0	R	643.92		639.86	639.76			72 - DIA 12"	71 - DIA 12"	DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
075	4' DIA CB TY A	T24	59+26.90	67.0	R	644.66			640.21				72 - DIA 12"	DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
076	4' DIA CB TY A	T24	60+98.34	99.0	R	642.65	635.71			73 - DIA12"				DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
077	4' DIA CB TY A	T8	61+76.49	84.1	L	640.40		637.04				74 - DIA 12"		DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
078	4' DIA CB TY A	T24	61+76.93	61.0	L	641.12		636.34	636.84			75 - DIA 18"	74 - DIA 12"	DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
079	5' DIA MH TY A	T1F, CL	61+69.47	77.9	R	643.75	632.50	635.00	633.50	77 - DIA36"	73 - DIA12"	76 - DIA 24"	75 - DIA 18"	DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
079A	5' DIA MH TY A	T1F, CL	62+38.50	94.6	R	642.53	632.33	632.33		78 - DIA36"	77 - DIA36"			DR-03	
080	4' DIA CB TY A	T24	63+63.00	61.0	L	640.20		635.76				79 - DIA 12"		DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
081	4' DIA CB TY A	T24	63+63.00	9.0	R	641.74		635.12	635.12			80 - DIA 12"	79 - DIA 12"	DR-03	
082	4' DIA CB TY A	T24	63+63.00	15.0	R	641.75		634.58	635.08			81 - DIA 18"	80 - DIA 12"	DR-03	
083	4' DIA CB TY A	T24	63+63.00	69.0	R	643.17		634.11	634.11			82 - DIA 18"	81 - DIA 18"	DR-03	
084	5' DIA MH TY A	T1F, CL	63+63.00	81.6	R	642.63	632.02	632.02	634.00	83 - DIA36"	78 - DIA36"		82 - DIA 18"	DR-03	
085	4' DIA CB TY A	T8	64+96.00	84.0	L	637.10		633.46				84 - DIA 12"		DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
086	4' DIA CB TY A	T24	64+96.00	61.0	L	639.53		633.26	633.26			85 - DIA 12"	84 - DIA 12"	DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
087	4' DIA CB TY A	T24	64+96.00	9.0	R	641.08		632.62	632.62			86 - DIA 12"	85 - DIA 12"	DR-03	
088	4' DIA CB TY A	T24	64+96.00	15.0	R	641.09		632.58	632.58			87 - DIA 12"	86 - DIA 12"	DR-03	
089	4' DIA CB TY A	T24	64+96.00	69.0	R	642.46		632.11	632.11			88 - DIA 12"	87 - DIA 12"	DR-03	
090	5' DIA MH TY A	T1F, CL	64+96.00	81.6	R	641.65	631.69	631.69	632.00	89 - DIA36"	83 - DIA36"		88 - DIA 12"	DR-03	
091	4' DIA CB TY A	T24	66+29.00	61.0	L	638.87		635.26				90 - DIA 12"		DR-03	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
092	4' DIA CB TY A	T24	66+29.00	9.0	R	640.42		634.62	634.62			91 - DIA 12"	90 - DIA 12"	DR-03	
093	4' DIA CB TY A	T24	66+29.00	15.0	R	640.43		634.58	634.58			92 - DIA 12"	91 - DIA 12"	DR-03	
094	4' DIA CB TY A	T24	66+29.00	69.0	R	641.79		634.11	634.11			93 - DIA 12"	92 - DIA 12"	DR-03	
095	5' DIA MH TY A	T1F, CL	66+29.00	81.6	R	641.24	631.36	631.36	634.00	94 - DIA36"	89 - DIA36"		93 - DIA 12"	DR-03	
096	4' DIA CB TY A	T24	67+62.00	61.0	L	638.21		632.30				95 - DIA 18"		DR-03	
097	4' DIA CB TY A	T24	67+62.00	4.2	R	639.83		631.70	631.70			96 - DIA 18"	95 - DIA 18"	DR-03	
098	4' DIA CB TY A	T24	67+62.00	15.0	R	639.76		631.61	631.61			97 - DIA 18"	96 - DIA 18"	DR-03	
099	4' DIA CB TY A	T24	67+62.00	69.0	R	641.13		631.14	631.14			98 - DIA 18"	97 - DIA 18"	DR-03	
100	5' DIA MH TY A	T1F, CL	67+62.00	81.6	R	641.34	631.03	631.03	631.03	99 - DIA36"	94 - DIA36"		98 - DIA 18"	DR-03	
101	4' DIA CB TY A	T24	68+95.00	61.0	L	637.55		631.96				100 - DIA 18"		DR-04	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
102	4' DIA CB TY A	T24	68+95.00	7.0	L	639.22		631.48	631.48			101 - DIA 18"	100 - DIA 18"	DR-04	
103	4' DIA CB TY A	T24	68+95.00	15.0	R	639.10		631.28	631.28			102 - DIA 18"	101 - DIA 18"	DR-04	
104	4' DIA CB TY A	T24	68+95.00	69.0	R	640.47		630.81	630.81			103 - DIA 18"	102 - DIA 18"	DR-04	
105	5' DIA MH TY A	T1F, CL	68+95.00	81.3	R	640.36	630.70	630.70	630.70	104 - DIA36"	99 - DIA36"		103 - DIA 18"	DR-04	
106	4' DIA CB TY A	T8	69+99.36	84.0	L	634.30		631.90				105 - DIA 12"		DR-04	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
107	4' DIA CB TY A	T24	69+99.36	61.0	L	637.22		631.70	631.70			106 - DIA 18"	105 - DIA 12"	DR-04	
108	4' DIA CB TY A	T24	69+99.36	14.2	L	638.77		631.29	631.29			107 - DIA 18"	106 - DIA 18"	DR-04	
109	4' DIA CB TY A	T24	69+99.36	14.8	R	638.77		631.02	631.02			108 - DIA 18"	107 - DIA 18"	DR-04	
110	4' DIA CB TY A	T24	69+99.36	69.9	R	640.14		630.56	630.56			109 - DIA 18"	108 - DIA 18"	DR-04	
111	5' DIA MH TY A	T1F, CL	69+99.36	81.1	R	639.20	630.45	630.45	630.45	113A - DIA36"	104 - DIA36"		109 - DIA 18"	DR-04	
112	4' DIA CB TY A	T24	70+05.00	61.0	L	637.22		632.75				110 - DIA 12"		DR-04	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
113	4' DIA CB TY A	T24	70+05.00	14.5	L	638.78		632.34	632.34			111 - DIA 12"	110 - DIA 12"	DR-04	
114	4' DIA CB TY A	T24	70+05.00	15.0	R	638.78		632.07	632.07			112 - DIA 12"	111 - DIA 12"	DR-04	
115	4' DIA CB TY A	T24	70+05.00	69.9	R	640.15		631.61	631.61			113 - DIA 12"	112 - DIA 12"	DR-04	
116	5' DIA MH TY A	T1F, CL	70+05.00	81.2	R	639.07	630.45	630.45	631.50	114 - DIA36"	113A - DIA36"		113 - DIA 12"	DR-04	
117	4' DIA CB TY A	T24	70+61.00	60.3	L	637.35		632.29				115 - DIA 12"		DR-04	
118	4' DIA CB TY A	T24	70+61.00	4.3	L	638.63		631.78	631.78			115A - DIA 12"	115 - DIA 12"	DR-04	
118A	4' DIA CB TY A	T24	70+61.00	4.3	R	638.56		631.73	631.73			116 - DIA 12"	115A - DIA 12"	DR-04	
119	4' DIA CB TY A	T24	70+61.00	70.9	R	640.26		631.11	631.11			117 - DIA 12"	116 - DIA 12"	DR-04	
120	6' DIA MH TY A	T1F, CL	70+61.00	81.9	R	637.88	629.29	630.29	631.00	118 - DIA48"	114 - DIA36"		117 - DIA 12"	DR-04	
121	4' DIA CB TY A	T24	72+00.00	58.4	L	638.03		633.37				119 - DIA 12"		DR-04	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
122	4' DIA CB TY A	T20	72+00.00	5.1	L	639.30		632.85	632.85			119A - DIA 12"	119 - DIA 12"	DR-04	
122A	4' DIA CB TY A	T20	72+00.00	3.9	R	639.46		632.30	632.80			120 - DIA 18"	119A - DIA 12"	DR-04	
123	NOT USED														
124	NOT USED														
125	6' DIA MH TY A	T1F, OL	72+00.00	88.3	R	637.87	628.88	628.88	631.50	123 - DIA48"	118 - DIA48"		120 - DIA 18"	DR-04	
126	4' DIA CB TY A	T24	73+91.00	57.5	L	639.01		634.82				124 - DIA 12"		DR-04	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
127	DRAINAGE STRUCTURE TYPE 1	T20	73+91.00	0.0		640.25		633.80	634.30			125 - DIA 18"	124 - DIA 12"	DR-04	
128	NOT USED														
129	5' DIA MH TY A	T1F, CL	73+50.00	92.9	R	639.49		628.43	628.43	123 - DIA48"		125 - DIA 18"		DR-04	
130	5' DIA MH TY A	T1F, CL	78+71.00	9.0	L	642.88		625.90	626.90	131 - DIA24"		131A - DIA 24"	132 - DIA 12"	DR-04	
131	4' DIA CB TY A	T20	76+64.05	56.7	L	641.73		629.91				128 - DIA 12"		DR-04	REPLACE CONE RISER WITH REINFORCED FLAT SLAB TOP
132	DRAINAGE STRUCTURE TYPE 1	T20	76+21.00	0.0		641.43		629.20	629.20			129 - DIA 12"	128 - DIA 12"	DR-04	
133	5' DIA MH TY A	T1F, CL	76+21.00	56.9	R	642.50	627.69		628.69	130 - DIA24"		129 - DIA 12"		DR-04	
134	5' DIA MH TY A	T1F, CL	77+98.77	4.2	L	642.33	626.50		627.74	131 - DIA24"				DR-04	WEST INVERT FROM PROPOSED PIPE ON DR-09
135	4' DIA CB TY A	T20	78+71.00	60.6	L	642.83		627.37				132 - DIA 12"		DR-04	
136	DRAINAGE STRUCTURE TYPE 1	T20	78+71.00	0.0		642.70		625.87	625.87			133 - DIA 24"	131A - DIA 24"	DR-04	
137	4' DIA CB TY A	T24	78+71.00	57.5	R	642.49		625.36	625.36			134 - DIA 24"	133 - DIA 24"	DR-04	
138	5' DIA MH TY A	T1F, OL	78+71.00	74.7	R	640.12	625.23	625.23	625.23	135 - DIA24"	130 - DIA24"		134 - DIA 24"	DR-04	
139	NOT USED														
140	6' DIA MH TY A	T1F, CL	79+90.00	83.2	R	641.66	624.09	624.09	624.09	137 - DIA48"	135 - DIA24"			DR-04	
141	NOT USED														
142	DRAINAGE STRUCTURE TYPE 1	T20	81+21.00	0.0		643.97		635.23				139 - DIA 12"		DR-04	
143	4' DIA CB TY A	T24	81+21.00	57.5	R	643.61		634.21	634.71			140 - DIA 18"	139 - DIA 12"	DR-04	
144	6' DIA MH TY A	T1F, CL	81+21.00	82.8	R	641.91	623.84	623.84	634.00	142 - DIA48"	137 - DIA48"		140 - DIA 18"	DR-04	



USER NAME = mikosir	DESIGNED MAM/PMS	REVISED -
	DRAWN PMS	REVISED -
PLOT SCALE = 50:1	CHECKED MAM	REVISED -
PLOT DATE = 19-OCT-2012	DATE 10/19/12	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

DRAINAGE STRUCTURE SCHEDULE

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105 WRS&HB	COOK	605	188
CONTRACT NO. 60G37				
ILLINOIS FED. AID PROJECT				