

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003	0040	0040	0040	0040	0010	0010	0021	0021	0021	0021	0028	0028	0003	0003
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
X	PERMANENT PAVEMENT MARKING LINE 10'	FOOT	2100															2100
X	X8630104 CONTROLLER CABINET TYPE IV, SPECIAL	EACH	1									1						
X	X8570231 FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1									1						
	JI442005 HOT-MIX ASPHALT PRESSURE RELIEF JOINT, CLASS D1 PATCHES, 12 INCHES	SQ YD	18															18
	JT726040 REMOVE AND REINSTALL MILEPOST MARKER	EACH	4															4
X	X8251388 LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200 AMP (DUAL), RADIO SCADA	EACH	1								1							
X	JS810100 UNDERGROUND CONDUIT, PVC COATED GALVANIZED STEEL, 4" DIA.	FOOT	591															591
X	JS830003 GROUND MOUNTED LIGHT POLE, ALUMINUM, 50 FT., 15 FT. MAST ARM	EACH	3															3
X	X0327486 TEMPORARY WOOD POLE, 60', CLASS 4, INSTALL ONLY	EACH	4								4							
X	JS830045 TEMPORARY WOOD POLE, 90 FT., CLASS 2, WITH 15 FT. MAST ARM, EMBEDDED	EACH	28															28
X	X0324243 CCTV VIDEO CODEC	EACH	4								4							
X	B2006125 TREE, SYRINGA PEKINENSIS ZHING ZHING (BEIJING GOLD PEKING LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	13	13														

X SPECIALTY ITEM

- A ROADWAY AND DRAINAGE - 100% STATE
- B RETAINING WALL SN 022-W063 - 100% STATE
- C RETAINING WALL SN 022-W064 - 100% STATE
- D RETAINING WALL SN 022-W065 - 100% STATE
- E RETAINING WALL SN 022-W066 - 100% STATE
- F BRIDGE SN 022-2029 - 100% STATE
- G BRIDGE SN 022-2030 - 100% STATE

- H LIGHTING - 100% STATE
- I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE
- J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE
- K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE
- L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE

- M SHARED-USE PATH - 100% NAPERVILLE
- N ROADWAY ITEMS - 100% STATE
- O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE #		DRAWN	REVISED			338	(112 & 113) WRS-6	DUPAGE	963	45
PLAT SCALE / DOUBLE		CHECKED	REVISED			CONTRACT NO. 60131				
PLAT DATE		DATE	REVISED			ILLINOIS FED. AID PROJECT				