

TREE REMOVAL (6 TO 15 UNITS DIAMETER)				
TREE #	STATION	OFFSET	LT/RT	QUANTITY UNIT
9041	4046+59	75	LT	14
9052	4048+72	89	LT	15
9061	4053+38	119	LT	12
10001	4059+99	47	RT	6
10002	4060+01	40	RT	6
10003	4064+32	121	LT	15
10004	4064+45	135	LT	12
10006	4064+75	119	LT	6
10010	4069+17	97	LT	15
10011	4069+26	96	LT	15
10012	4069+76	93	LT	15
10013	4069+83	91	LT	15
10014	4065+54	99	RT	6
20001	1996+74	112	LT	6
20002	1996+77	95	LT	6
20003	1996+81	99	LT	6
20004	1996+96	121	LT	6
20005	1997+03	99	LT	6
20006	1997+08	121	LT	6
20007	1997+11	115	LT	6
20008	1997+13	79	LT	6
20009	1997+20	156	LT	6
20010	1997+28	138	LT	6
20011	1997+36	95	LT	6
21000	1004+15	60	RT	14
21001	1004+78	58	RT	15
PROJECT TOTAL				247

FENCE REMOVAL					
FROM	OFFSET	TO	OFFSET	LT/RT	QUANTITY FOOT
1001+11	67.0	1005+06	36.5	RT	397
4065+71	111.1	4066+71	87.2	LT	103
PROJECT TOTAL					500

MEDIAN REMOVAL			
FROM	TO	LT/RT	QUANTITY SQ FT
4054+81	4057+21	RT	892
4059+45	4061+58	LT	790
4073+27	4077+51	LT	2491
PROJECT TOTAL			4173

DRIVEWAY PAVEMENT REMOVAL			
FROM	TO	LT/RT	QUANTITY SQ YD
4072+51	4073+89	LT	360
PROJECT TOTAL			360

HOT-MIX ASPHALT SURFACE REMOVAL, 2"			
FROM	TO	LT/RT	QUANTITY SQ YD
4070+44	4073+70	LT	1014
4073+70	4077+51	LT	1621
4072+43	4074+00	RT	413
4074+00	4077+51	RT	1264
PROJECT TOTAL			4312

PAVED SHOULDER REMOVAL			
FROM	TO	LT/RT	QUANTITY SQ YD
1001+50	1041+55	LT	4417
1002+00	1012+85	LT	484
1986+78	1998+40	RT	1341
1986+78	1998+84	LT	632
6526+45	6528+41	RT	225
6526+56	6528+72	RT	302
6526+56	6528+72	LT	314
6526+68	6528+69	LT	229
7001+24	7014+73	RT	710
7001+24	7014+73	LT	1507
8959+48	8967+53	LT	1005
8990+83	8999+34	LT	411
8996+64	8998+96	RT	246
PROJECT TOTAL			11824

GUARDRAIL REMOVAL					
FROM	OFFSET	TO	OFFSET	LT/RT	QUANTITY FOOT
1000+09	89.6	1003+04	3.4	RT	339
1001+96	46.1	1010+60	30.2	LT	868
1010+54	5.4	1023+07	2.7	RT	1581
4053+51	37.0	4057+01	35.5	LT	350
4054+25	38.6	4057+24	35.6	RT	302
4059+53	35.2	4062+24	44.4	LT	272
4059+65	37.1	4062+14	38.1	RT	249
4067+33	45.5	4068+06	43.0	RT	73
6523+39	66.6	6534+52	65.9	RT	1113
6528+25	64.1	6531+31	66.8	LT	306
8965+50	8.3	8967+15	15.6	RT	165
8967+39	15.5	8999+72	87.6	RT	3256
PROJECT TOTAL					8874

TREE REMOVAL (OVER 15 UNITS DIAMETER)				
TREE #	STATION	OFFSET	LT/RT	QUANTITY UNIT
9035	4045+37	72	LT	24
9036	4045+59	76	LT	32
9037	4046+21	72	LT	16
9039	4046+37	80	LT	16
9046	4047+64	78	LT	28
9051	4048+60	84	LT	18
10007	4064+94	119	LT	18
10009	4067+34	95	LT	18
PROJECT TOTAL				170