

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE N. BRANCH CHICAGO RIVER	BRIDGE OVER I-94 EDENS EXPY	TRAFFIC SIGNALS																100% G L E N V I E W
							WILLOW RD AT IL ROUTE 43	WILLOW RD AT THREE LAKES DRIVE	WILLOW RD AT SUNSET RIDGE ROAD	WILLOW RD AT WAGNER RD	WILLOW RD AT PED ONLY CROSSING	WILLOW RD AT OLD WILLOW / NORTHFIELD RD	WILLOW RD AT CENTRAL AV / HAPP ROAD	IL ROUTE 43 AT THREE LAKES DRIVE	INTERCONNECT								
							80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	
0003	0010	0014	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0003			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	98607	98607																			
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	275	275																			
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	549	549																			
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	689	689																			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	290	290																			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24																			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1924	1924																			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	162	162																			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	293	293																			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	36	36																			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	429	429																			
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	332	332																			
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	2965	2965																			
42000406	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	SQ YD	55304	55304																			
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	14074	14074																			
42001300	PROTECTIVE COAT	SQ YD	31285	31285																			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	43	43																			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	125	125																			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	80582	80582																			
42400800	DETECTABLE WARNINGS	SQ FT	1522	1522																			
44000100	PAVEMENT REMOVAL	SQ YD	72221	72221																			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	184	184																			
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	204	204																			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2091	2091																			
44000300	CURB REMOVAL	FOOT	310	310																			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16752	16752																			
44000600	SIDEWALK REMOVAL	SQ FT	46932	46932																			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	218	218																			
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	262	262																			
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	345	345																			
44003100	MEDIAN REMOVAL	SQ FT	7186	7186																			

\* DENOTES SPECIALTY ITEM  
 \$ 80% FEDERAL, 20% NORTHFIELD (ITEP)  
 + 90% STATE, 10% NORTHFIELD  
 & 40% STATE, 60% NORTHFIELD  
 # 100% NORTHFIELD  
 NP NON-PARTICIPATING ITEM