CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE N. BRANCH CHICAGO RIVER	BRIDGE OVER I-94 EDENS EXPY	TRAFFIC SIGNALS: WILLOW RD AT IL ROUTE 43	WILLOW RD AT THREE LAKES DRIVE	WILLOW RD AT SUNSET RIDGE ROAD		WILLOW RD AT WAGNER RD		WILLOW RD AT PED ONLY CROSSING		WILLOW RD AT OLD WILLOW / NORTHFIELD RD		WILLOW RD AT CENTRAL AV / HAPP ROAD		IL ROUTE 43 AT THREE LAKES DRIVE		INTERCONNECT				100% GLENVIEW
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE				
				0003	0010	0014	0021	0021	0021		0021		0021		0021		0021		0021		0021				0003
44004250	PAVED SHOULDER REMOVAL	SQ YD	3526	3526																					
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	3	3																					
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	141	141																					
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	212	212																					
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	311	311																					
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	13	13																					
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	57	57																					
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	103	103																					
48101500	AGGREGATE SHOULDERS, TYPE B 6*	SQ YD	45	45																					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	151	151																					
48203027	HOT-MIX ASPHALT SHOULDERS, 7 1/2*	SQ YD	182	182																					
48203046	HOT-MIX ASPHALT SHOULDERS, 12 1/4*	SQ YD	3372	3372																					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1																				
50102400	CONCRETE REMOVAL	CU YD	68.3			68.3																			
50104000	BRIDGE RAIL REMOVAL	FOOT	464			464																			
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3																					
50157300	PROTECTIVE SHIELD	SQ YD	85			85																			
50200100	STRUCTURE EXCAVATION	CU YD	894	459	435																				
50300225	CONCRETE STRUCTURES	CU YD	104	1.5	102.5																				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	773.6	190.6	506	77																			
50300260	BRIDGE DECK GROOVING	SQ YD	707		707																				
50300285	FORM LINER TEXTURED SURFACE	SQ FT	4673	3028	1645																				
50300300	PROTECTIVE COAT	SQ YD	2039	430	1293	316																			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1																				
50500505	STUD SHEAR CONNECTORS	EACH	4191		4191																				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	162486	24396	126510	11580																			
50800515	BAR SPLICERS	EACH	693		693																				
50901730	BRIDGE FENCE RAILING	FOOT	464			464																			
51200959	FURNISHING METAL SHELL PILES 14" X 0.312*	FOOT	1734		1734																				
51202305	DRIVING PILES	FOOT	1734		1734																				
51203200	TEST PILE METAL SHELLS	EACH	2		2																				
51204650	PILE SHOES	EACH	30		30																				

* DENOTES SPECIALTY ITEM
$ 80% FEDERAL, 20% NORTHFIELD (ITEP)
+ 90% STATE, 10% NORTHFIELD
& 40% STATE, 60% NORTHFIELD
# 100% NORTHFIELD
NP NON-PARTICIPATING ITEM

Rev.

FILE NAME = G:\CHI\0150\Road\Sheets\D168T35-SHT-SQ001.dgn	USER NAME = mnbaldwin	DESIGNED - JLV	REVISED -
		DRAWN - JRS	REVISED -
	PLOT SCALE = 40.000 ' / in.	CHECKED - RCB	REVISED -
	PLOT DATE = 11/1/2012	DATE - 10/31/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. | SHEET NO. 6 OF 919 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	(1920.01,1518,2022&1922.4B)R	COOK	919	6

CONTRACT NO. 60T35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT