CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE N. BRANCH CHICAGO RIVER	BRIDGE OVER I-94 EDENS EXPY	TRAFFIC SIGNALS: WILLOW RD AT IL ROUTE 43	WILLOW RD AT THREE LAKES DRIVE	WILLOW RD AT SUNSET RIDGE ROAD		WILLOW RD AT WAGNER RD		WILLOW RD AT PED ONLY CROSSING		WILLOW RD AT OLD WILLOW / NORTHFIELD RD		WILLOW RD AT CENTRAL AV / HAPP ROAD		IL ROUTE 43 AT THREE LAKES DRIVE		INTERCONNECT	LIGHTING		100% GLENVIEW
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% STATE	50% FED 50% NFIELD ITEP	
				0003	0010	0014	0021	0021	0021		0021		0021		0021		0021		0021		0021	0021		0003
* 81400300	DOUBLE HANDHOLE	EACH	15				4	2	2		2		1		2		2							
* 81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	3217																			3217		
* 81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	40																			40		
* 81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	50																			50		
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	738																			738		
* 81800330	AERIAL CABLE, 3-1/C NO. 6 WITH MESSENGER WIRE	FOOT	1375																			1375		
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	14																			14		
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	7																			7		
* 82500370	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 200AMP	EACH	1																			1		
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	7																			7		
* 83057225	LIGHT POLE, WOOD, 40 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	3																			3		
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	300																			300		
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	7																			7		
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	3																			3		
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	10																			10		
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	12																			12		
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3																			3		
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1																			1		
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2																		2			
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	7				1	1	1		1		1		1		1							
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	14662																		14662			
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	8954				1660	1608	1274		1303		180		1308		1621							
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	12894				2780	2545	1635		1679		290		1645		2320							
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	13532				3943	2874	1197		1270		1052		1174		2022							
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	9904				1802	923	1985		1523				1514		2157							
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1PAIR	FOOT	18256				6328	1707	2460		2407		692		2154		2508							
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	749				80	45	60		113		115		234		102							
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	5418				925	781	669		769		519		894		861							
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4				4																	
* 87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1				1																	
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1				1																	
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1				1																	

* DENOTES SPECIALTY ITEM
$ 80% FEDERAL, 20% NORTHFIELD (ITEP)
\+ 90% STATE, 10% NORTHFIELD
& 40% STATE, 60% NORTHFIELD
\# 100% NORTHFIELD
NP NON-PARTICIPATING ITEM

Rev.

FILE NAME = G:\CHI\0158\Road\Sheets\D160135-SHT-S0001.dgn	USER NAME = mmbaldwin	DESIGNED - JLV	REVISED -
		DRAWN - JRS	REVISED -
	PLOT SCALE = 40.000 ' / in.	CHECKED - RCB	REVISED -
	PLOT DATE = 11/1/2012	DATE - 10/31/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. | SHEET NO. 14 OF 919 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	(1920.01,1518.2022&1922.4B)R	COOK	919	14
		CONTRACT NO. 60T35		
	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	