	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE N. BRANCH CHICAGO RIVER	BRIDGE OVER I-94 EDENS EXPY	TRAFFIC SIGNALS: WILLOW RD AT IL ROUTE 43	WILLOW RD AT THREE LAKES DRIVE	WILLOW RD AT SUNSET RIDGE ROAD		WILLOW RD AT WAGNER RD		WILLOW RD AT PED ONLY CROSSING		WILLOW RD AT OLD WILLOW / NORTHFIELD RD		WILLOW RD AT CENTRAL AV / HAPP ROAD		IL ROUTE 43 AT THREE LAKES DRIVE		INTERCONNECT	LIGHTING		100% GLENVIEW
					80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% STATE	50% FED 50% NFIELD ITEP	
					0003	0010	0014	0021	0021	0021		0021		0021		0021		0021		0021		0021			0003
*	87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1				1																	
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	86				20	12	12		16		16		8		12							
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	28				4	4	4		4		4		4		4							
*	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4	4																				
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	51												37		14							
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	260				56	38	46		44		22		13		39							
*	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	25					25																
*	87900200	DRILL EXISTING HANDHOLE	EACH	6																		3	3		
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	50				12	9	6		6		4		6		7							
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1					1																
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	12						3		3				4		2							
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	24				4	2	5		4				4		5							
*	88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2										2											
*	88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2						1								1							
*	88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	8				4	2			1						1							
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	38				8	4	8		8		2		4		6							
*	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6					2	1						2		1							
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	74				16	11	11		10		4		10		12							
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	68				19	7	11		10		2		9		10							
*	88600100	DETECTOR LOOP, TYPE I	FOOT	93					93																
*	88600700	PREFORMED DETECTOR LOOP	FOOT	5828				936	861	1007		901		118		931		1074							
# *	88700200	LIGHT DETECTOR	EACH	17				4	3	2		2		1		2		3							
# *	88700300	LIGHT DETECTOR AMPLIFIER	EACH	7				1	1	1		1		1		1		1							
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	50				8	8	8		8		2		8		8							
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	7				1	1	1		1				1		1		1					
*	89500510	CABINET HOUSING EQUIPMENT REMOVAL	EACH	1	1																				
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	6542																		6542			
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	6				1	1	1		1				1		1							
*	89502376	REBUILD EXISTING HANDHOLE	EACH	1																		1			
*	89502380	REMOVE EXISTING HANDHOLE	EACH	67				14	9	10		10				8		14				2			
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	56	1			10	9	9		9				9		9							
*	A2000220	TREE, ACER X FREEMANII MARMO (MARMO FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5																				

* DENOTES SPECIALTY ITEM
$ 80% FEDERAL, 20% NORTHFIELD (ITEP)
+ 90% STATE, 10% NORTHFIELD
& 40% STATE, 60% NORTHFIELD
# 100% NORTHFIELD
NP NON-PARTICIPATING ITEM

FILE NAME = G:\CHI1\0160\Road\Sheets\0160T35-SHT-SQ001.dgn	USER NAME = mnbaldwin	DESIGNED - JLV	REVISED -
		DRAWN - JRS	REVISED -
	PLOT SCALE = 40.000 ' / in.	CHECKED - RCB	REVISED -
	PLOT DATE = 11/1/2012	DATE - 10/31/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. | SHEET NO. 15 OF 919 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	(1920.01,1518,2022&1922.4B)R	COOK	919	15

CONTRACT NO. 60T35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT