

1056 1220 1056 0700 1160  
24 02 01 01 01

80% NF  
20% NF  
S

① ② ③ ④ ⑤ ⑥ ⑦ ⑧ ⑨ ⑩ ⑪ ⑫ ⑬ ⑭ ⑮ ⑯ ⑰ ⑱ ⑲ ⑳

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS																					LIGHTING	UTILITIES	100% GLENVIEW					
				ROADWAY		BRIDGE N. BRANCH CHICAGO RIVER		BRIDGE OVER I-94 EDENS EXPY		WILLOW RD AT IL ROUTE 43		WILLOW RD AT THREE LAKES DRIVE		WILLOW RD AT SUNSET RIDGE ROAD		WILLOW RD AT WAGNER RD		WILLOW RD AT PED ONLY CROSSING		WILLOW RD AT OLD WILLOW / NORTHFIELD RD		WILLOW RD AT CENTRAL AV / HAPP ROAD		IL ROUTE 43 AT THREE LAKES DRIVE				INTERCONNECT	80% FED 20% STATE	80% FED 20% STATE	50% FED 50% NFIELD ITEP	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP									
0003	0010	0014	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0043	0003						
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12																								12					
* Z0033040	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	3																								3					
* Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1																								1					
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	2036	2036																												
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	184		184																											
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	2657	2139																									518			
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	104	72																									32			
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	114	85																									29			
Z0056620	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	40	28																									12			
Z0056622	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	25	25																												
Z0056624	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	111	111																												
* Z0056900	SANITARY SEWER 8"	FOOT	358																										223			
* Z0057000	SANITARY SEWER 10"	FOOT	1428																										1428			
* Z0057200	SANITARY SEWER 15"	FOOT	349																										349			
Z0062456	TEMPORARY PAVEMENT	SQ YD	17849	17849																												
Z0062458	TEMPORARY PAVEMENT (VARIABLE DEPTH)	TGN	522	522																												
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	402	146	256																											
Z0073346	SLEEPER SLAB	SQ YD	637	637																												
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	7						1	1	1	1			1						1											
<del>Z0076800</del>	<del>TRAINEES</del>	<del>HOUR</del>	<del>5000</del>	<del>5000</del>																												
* K1001988	IRRIGATION SYSTEM SPECIAL	L SUM	1																											1.8		
* X0327572	SANITARY FORCE MAIN, 4"	FOOT	3241																										3241			
* X6640550	CHAIN LINK FENCE, 4" (SPECIAL)	FOOT	293	293																												
<del>* Z0076800</del>	<del>ILLUMINATED SIGN</del>	<del>EACH</del>	<del>20</del>																													
X7010218	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	EACH	1	1																												
X7200995	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	SQ YD	6145	6145																												
X4201015	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	1564	1564																												
* X5631004	CUT AND CAP EXISTING 4" FORCE MAIN	EACH	2																										2			
* X5631104	CONNECTION TO EXISTING FORCE MAIN 4"	EACH	2																										2			
* 81603063	UNIT DUCT, 600V, 4-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1450																										1450			
* X8162815	UNIT DUCT, 600V, 2-1C NO.2, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1-1/2" DIA. POLYETHYLENE	FOOT	2811																										2811			
* 81702417	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO.6, 1/C NO.6 GROUND	FOOT	315																										315			

\* DENOTES SPECIALTY ITEM  
\$ 80% FEDERAL, 20% NORTHFIELD (ITEP)  
+ 90% STATE, 10% NORTHFIELD  
& 40% STATE, 60% NORTHFIELD  
# 100% NORTHFIELD  
NP NON-PARTICIPATING ITEM

FILE NAME : G:\CHINA\Roads\Sheets\1060105-SH1-5081.dgn	USER NAME : embalwin	DESIGNED : JLV	REVISED :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE. : 305	SECTION : 11920.01.1518.2022&1922.48R	COUNTY : COOK	TOTAL SHEETS : 919	SHEET NO. : 20A
PLOT SCALE : 48,000 ' / 1"	PLOT DATE : 11/1/2012	CHECKED : RCB	REVISIED :	SCALE : N.T.S.				SHEET NO. 20A OF 919 SHEETS				CONTRACT NO. 60T35				
		DATE : 10/31/2012										FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.