

SCHEDULE OF PCC PAVEMENT													
FROM	TO	PCC PVMT LENGTH (FT)	WIDTH OF LANES (FT)	AREA OF LANES (SQ FT)	AREA OF TURN BAYS (SQ FT)	ADDITIONAL AREA (SQ FT)	30300112 AGG SUBGRADE IMPR 12 (SQ YD)	42000406 PCC PVT 9 1/4 JOINTD (SQ YD)	HES PCC PVT 9 1/4 JOINTD (SQ YD)	42000506 PCC PVT 10 1/4 JOINTD (SQ YD)	HES PCC PVT 10 1/4 JOINTD (SQ YD)	42001300 PROTECTIV E COAT (SQ YD)	44000100 PAVEMENT REM (SQ YD)
WILLOW ROAD													
625+00	637+00	542	VARIES 44-48	24,226	13,411		4,849	4,182				1,045	4,444
637+00	649+00	1,095	VARIES 44-48	70,435	32,459	16,044	14,727	8,901		4,314		3,304	12,490
649+00	661+00	1,200	VARIES 40-44	50,777	8,993	13,883	9,283	8,104				2,026	9,845
661+00	672+00	1,100	VARIES 40-42	44,513	8,852	18,847	9,101	8,024				2,006	6,633
672+00	683+00	1,100	42	46,200	774	7,973	6,927	6,105				1,526	3,955
683+00	693+00	1,000	42	42,000	400	4,260	5,885	5,184				1,296	3,153
693+00	704+00	1,100	VARIES 40-42	44,743	4,883	12,395	7,960	6,891				1,723	5,726
704+00	716+00	1,056	40	42,220	4,317	5,120	6,441	5,740				1,435	4,315
716+00	728+00	1,200	VARIES 40-48	43,908	6,680	24,275	6,441	8,318				2,080	9,383
728+00	740+00	1,076					158						606
ILLINOIS ROUTE 43													
493+00	505+00						40						
505+00	518+00	592	60	35,560	14,765		6,572			5,592		1,398	5,073
518+00	530+50	745	48	35,747	14,002	1,839	6,654			5,732		1,433	6,053
SUBTOTAL							88,116	61,449		15,638		19,272	71,676
HIGH EARLY STRENGTH (ASSUME 10%)								-6,145	6,145		-1,564	1,564	
OVERALL TOTAL							88,116	55,304	6,145	14,074	1,564	19,272	71,676

NOTE 1 AGGREGATE SUBGRADE QUANTITY INCLUDES AREA FOR CURB AND GUTTER LOCATIONS OUTSIDE THE PAVEMENT RECONSTRUCTION AREA.
NOTE 2 AGGREGATE SUBGRADE QUANTITIES INCLUDE AREA UNDER THE CURB AND GUTTER AND MEDIAN AS SHOWN ON THE TYPICALS.
NOTE 3 PROTECTIVE COAT QUANTITY INCLUDES 25% OF PCC PAVEMENT AREA. PROTECTIVE COAT FOR CURB AND GUTTER AND MEDIAN IS INCLUDED IN THE CURB AND GUTTER SCHEDULE.
* SEE OTHER SCHEDULES FOR ADDITIONAL QUANTITY

SCHEDULE OF HMA PAVEMENT - BUTT JOINTS AND RESURFACING																
FROM	TO	REQUIRED FOR HMA SC "D" N50			REQUIRED FOR HMA SC "D" N70			REQUIRED FOR HMA SC "F" N90			40600100 BIT MATLS PR CT (TON)	40603340 HMA SC "D" N70 (TON)	40600982 HMA SURF REM BUTT JT (SQ YD)	44000155 HMA SURF REM 11/2 (SQ YD)	44000156 HMA SURF REM 13/4 (SQ YD)	
		APP RATE HMA SURFACE (GALLON/SQ YD)	NO APPS HMA SURFACE	40600100 BIT MATLS PR CT (TON)	40603335 HMA SC "D" N50 (TON)	APP RATE HMA SURFACE (GALLON/SQ YD)	NO APPS HMA SURFACE	40600100 BIT MATLS PR CT (TON)	40603340 HMA SC "D" N70 (TON)	APP RATE HMA SURFACE (GALLON/SQ YD)						NO APPS HMA SURFACE
WILLOW ROAD																
625+00	637+00									0.10	1	0.1	12	240		
637+00	649+00															
649+00	661+00															
661+00	672+00	0.10	1	0.04	5	0.10	1	0.1	7				284			
672+00	683+00	0.10	1	0.03	3								68			
683+00	693+00	0.10	1	0.01	2								37			
693+00	704+00	0.10	1	0.12	13								309			
704+00	716+00	0.10	1	0.05	5								127			
716+00	728+00	0.10	1	0.16	24	0.10	1	0.1	16				583	184		
728+00	740+00															
ILLINOIS ROUTE 43																
493+00	505+00															
505+00	518+00									0.10	1	0.1	25	167	204	
518+00	530+50									0.10	1	0.1	14	285		
I-94																
413+00	435+00															
435+00	446+00															
I-94 RAMP A																
810+50	822+64															
I-94 RAMP D																
850+00	862+00															
862+00	872+56															
SUBTOTAL				0	52			0	23			0	51	2,100	184	204
OVERALL TOTAL				0	52			0	23			0	51	2,100	184	204

NOTE 1 AGGREGATE SUBGRADE QUANTITY INCLUDES AREA FOR CURB AND GUTTER LOCATIONS OUTSIDE THE PAVEMENT RECONSTRUCTION AREA.
NOTE 2 AGGREGATE SUBGRADE QUANTITIES INCLUDE AREA UNDER THE CURB AND GUTTER AND MEDIAN AS SHOWN ON THE TYPICALS.
NOTE 3 PROTECTIVE COAT QUANTITY INCLUDES 25% OF PCC PAVEMENT AREA. PROTECTIVE COAT FOR CURB AND GUTTER AND MEDIAN IS INCLUDED IN THE CURB AND GUTTER SCHEDULE.
* SEE OTHER SCHEDULES FOR ADDITIONAL QUANTITY

FILE NAME = G:\CH11\0158\Road\Sheets\0160T35-SHT-SCHE.Dgn	USER NAME = BAWtor.t	DESIGNED - JLV	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 1/8" = 1' / in.	CHECKED - RCB	REVISED -	305			(1920.01,1518,2022&1922.4)BR	COOK	919	36		
PLOT DATE = 11/30/2012	DATE - 10/31/2012	REVISED -	SCALE: N.T.S.			SHEET NO. 36 OF 919 SHEETS			CONTRACT NO. 60T35		
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					