

SCHEDULE OF DRAINAGE STRUCTURE REMOVALS AND ADJUSTMENTS								
STATION		50104400	60250200	60255500	60260100	60500040	60500050	60500060
FROM	TO	CONC HDWL REM EACH	CB ADJUST EACH	MAN ADJUST EACH	INLETS ADJUST EACH	REMOV MANHOLES EACH	REMOV CATCH BAS EACH	REMOV INLETS EACH
WILLOW ROAD								
625+00	637+00		1	3		1	4	2
637+00	649+00			1		3	11	
649+00	661+00	1				3	12	2
661+00	672+00		3			2	11	1
672+00	683+00							1
683+00	693+00					1	1	1
693+00	704+00			1		7	5	5
704+00	716+00	2				2		
716+00	728+00		3	2	2	6	7	8
728+00	740+00		1		2		1	
WAUKEGAN ROAD								
493+00	505+00							
505+00	518+00		2			1	2	
518+00	530+50					1	2	
INTERSTATE 94								
413+00	424+00			2			2	
424+00	435+00		1	4		1	3	
435+00	446+00							
TOTALS		3	11	13	4	28	61	20

SCHEDULE OF DRAINAGE PIPE REMOVAL															
STATION		55100200	55100300	55100400	55100500	55100700	55100900	55101100	55101200	55101300	55101400	55101600	55101800	X0324752	X5015225
FROM	TO	STORM SEWER REM 6 FOOT	STORM SEWER REM 8 FOOT	STORM SEWER REM 10 FOOT	STORM SEWER REM 12 FOOT	STORM SEWER REM 15 FOOT	STORM SEWER REM 18 FOOT	STORM SEWER REM 21 FOOT	STORM SEWER REM 24 FOOT	STORM SEWER REM 27 FOOT	STORM SEWER REM 30 FOOT	STORM SEWER REM 36 FOOT	STORM SEWER REM 42 FOOT	STORM SEWER FILLED CU YD	PIPE CULVERT REM SPL FOOT
WILLOW ROAD															
625+00	637+00				35				7						
637+00	649+00				380			303			183			0.4	
649+00	661+00	6			73						10			0.9	6
661+00	672+00	6	75	16	114	91	458	5		72	10			0.1	
672+00	683+00		26	11	53	81	67								
683+00	693+00			14	140	82									
693+00	704+00		67	56	222	205	1				6	498			
704+00	716+00		89			665	182		494			1,015	71		
716+00	728+00	17	95	186	764		168		104			733			
728+00	740+00														
WAUKEGAN ROAD															
493+00	505+00														
505+00	518+00				250		4								
518+00	530+50				8		61								
INTERSTATE 94															
413+00	424+00				25										
424+00	435+00				6	359								0.7	
435+00	446+00														
TOTALS		29	352	283	2,070	1,483	941	308	605	72	209	2,246	71	2.1	6