

SCHEDULE OF STORM SEWERS TO BE CLEANED											
STATION		X5537500	X5537700	X5537800	X5537900	X5538000	X5538100	X5538200	X5538300	X5538400	X5538900
FROM	TO	SS CLEANED 6 FOOT	SS CLEANED 10 FOOT	SS CLEANED 12 FOOT	SS CLEANED 15 FOOT	SS CLEANED 18 FOOT	SS CLEANED 21 FOOT	SS CLEANED 24 FOOT	SS CLEANED 27 FOOT	SS CLEANED 30 FOOT	SS CLEANED 54 FOOT
WILLOW ROAD											
625+00	637+00			374				722			
637+00	649+00			85			7	331			
649+00	661+00								316	1,593	
661+00	672+00			88			443			273	
672+00	683+00										
683+00	693+00										
693+00	704+00									4	
704+00	716+00										
716+00	728+00	40	32	55	149						
728+00	740+00			454		88					
WAUKEGAN ROAD											
493+00	505+00										
505+00	518+00			95		529					
518+00	530+50										
INTERSTATE 94											
413+00	424+00										393
424+00	435+00			24				147			975
435+00	446+00										
TOTALS		40	32	1,175	149	617	450	1,200	316	1,870	1,368

FILE NAME =	USER NAME = BAWtor.t	DESIGNED - JLV	REVISED -
G:\CH11\0158\Road\Sheets\0160T35-SHT-SCHED.dgn		DRAWN - MNB	REVISED -
	PLOT SCALE = 100.000' / in.	CHECKED - RCB	REVISED -
	PLOT DATE = 11/30/2012	DATE - 10/31/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 50 OF 919 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	(1920.01,1518,2022&1922.4B)R	COOK	919	50
CONTRACT NO. 60T35			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	