EXISTING SIGN NUMBER	PANEL DESCRIPTION	SIGN SUPPORT STATION OFFSET		FACING TRAFFIC	ACTION	DIMENSION W x H			
E2-23	(SHARED POST)	POST MOUNTED (GROUND)	643+75	75 39.3' RT			SIGN PANEL ASSEMBLY TO BE RELOCATED		
E2-23a	NO PARKING SNOW ROUTE		EB SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		24"	x 30"			
E2-23b	NO PARKING ON ANY VILLAGE STREET HOURS			EB SIGN PANEL TO BE RELOCATED WITH		SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	30"	x 36"	
E2-24	RIGHT TURN LANE	POST MOUNTED (GROUND)	644+53	49.9'	LT	WB	SIGN PANEL ASSEMBLY TO BE REMOVED	24"	x 24"
E2-25	(SHARED POST)	POST MOUNTED (GROUND)	644+87	37.2'	RT		SIGN PANEL ASSEMBLY TO BE RELOCATED		
E2-25a	LOVE THE LAND OF LINCOLN					EB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	30"	x 36"
E2-25b	ADOPT-A-HIGHWAY					EB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	30"	x 18"
E2-25c	KEEP ILLINOIS CLEAN					EB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	50"	x 25"
E2-26	BUCKLE UP	DUAL POST MOUNTED (GROUND)	646+16	37.0'	RT	EB	SIGN PANEL ASSEMBLY TO BE REMOVED	30"	x 30"
WILLOW ROAD (S	STA 649+00 TO STA 661+00)		-					•	
E3-1	(SHARED POST)	POST MOUNTED (GROUND)	651+67	142.7'	RT		POST TO REMAIN		
E3-1a	STOP SIGN					WB	SIGN TO REMAIN	30"	x 30"
E3-1b	2-WAY					WB	SIGN TO REMAIN	18"	x 6"
E3-2	NEIGHBORHOOD SPEED 20	POST MOUNTED (GROUND)	651+91	143.1'	RT	WB	SIGN AND POST TO REMAIN	18"	x 30"
E3-3	(SHARED POST)	MOUNTED ON SIGNAL POST MAST	651+97	44.2'	LT		SIGN PANEL ASSEMBLY TO BE REMOVED		
E3-3a	THREE LAKES DRIVE					EB	SIGN PANEL TO BE REMOVED WITH ASSEMBLY	48"	x 30"
E3-3b	THREE LAKES DRIVE					WB	SIGN PANEL TO BE REMOVED WITH ASSEMBLY	48"	x 30"
E3-4	KEEP RIGHT	MOUNTED ON DECORATIVE STREET LIGHT POLE	652+02	164.7'	RT	EB	SIGN AND POLE TO REMAIN		x 30"
E3-5	(SHARED POST)	POST MOUNTED (CONCRETE MEDIAN)	652+33	5.9'	LT		SIGN PANEL ASSEMBLY TO BE RELOCATED		
E3-5a	LEFT TURN ONLY					EB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	24"	x 30"
E3-5b	KEEP RIGHT					WB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		x 30"
E3-6	(SHARED POST)	MOUNTED ON SIGNAL POST	652+36	40.0'	RT		SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST		
E3-6a	DO NOT BLOCK INTERSECTION		332 33	10.0		EB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	24"	x 30"
E3-6b	FOLDED STOP SIGN					EB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		x 30"
E3-7	(SHARED POST)	POST MOUNTED (GROUND)	652+43	73.1'	LT		SIGN PANEL ASSEMBLY TO BE REMOVED		
E3-7a	THREE LAKES DR	1 OUT MOUNTED (ORGOND)	002110	70.1		WB	SIGN PANEL TO BE REMOVED WITH ASSEMBLY	36"	x 10"
E3-7b	WILLOW RD					SB	SIGN PANEL TO BE REMOVED WITH ASSEMBLY		x 10"
E3-8	FOLDED STOP SIGN	MOUNTED ON SIGNAL POST	652+47	81.2'	LT	SB	SIGN PANEL ASSEMBLY TO BE RELOCATED		x 30"
E3-9	WILLOW RD	MOUNTED ON SIGNAL POST MAST	652+60	52.5'	RT	SB	SIGN PANEL TO BE REMOVED		x 12"
E3-10	(SHARED POST)	POST MOUNTED (GROUND)	652+63	97.6'	LT	OB	SIGN PANEL ASSEMBLY TO BE RELOCATED		^ 12
E3-10a	FIRE LANE	1 GOT MICONTED (GROUND)	032103	37.0		WB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	24"	x 30"
E3-10a	FOR ACCESS TO THIS AREA					WB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		x 30"
E3-11	AREA MONITORED	POST MOUNTED (GROUND)	652+75	135.5'	LT	SB	SIGN AND POST TO REMAIN		x 24"
E3-12	KRAFT ENTRANCE SIGN	DUAL POST MOUNTED (LANDSCAPED MEDIAN)	653+13	111.5'	LT	NB	SEE NOTE 2		x 36"
E3-13	(SHARED POST)	DECORATIVE POST MOUNTED (LANDSCAPED MEDIAN)	653+19	67.6'	RT	ND	POST TO REMAIN	20	× 50
E3-13a	FOX MEADOW	DECONATIVE FOOT MODIVIED (LANDOCAL ED MEDIAN)	000119	07.0	IXI	EB	SIGN TO REMAIN	32"	x 37"
E3-13b	TO EDGEWOOD LN		+			EB	SIGN TO REMAIN		x 18"
E3-14	FOLDED STOP SIGN	MOUNTED ON SIGNAL POST	653+55	57.5'	RT	NB	SIGN PANEL TO BE RELOCATED		x 36"
E3-15	WILLOW RD	MOUNTED ON SIGNAL POST MAST	653+65	99.9'	LT	NB	SIGN PANEL TO BE REMOVED		x 12"
E3-16	DO NOT BLOCK INTERSECTION	MOUNTED ON SIGNAL POST	653+82	43.2'	RT	EB	SIGN PANEL TO BE RELOCATED ON NEW SIGNAL POST		x 30"
E3-17	(SHARED POST)	MOUNTED ON SIGNAL POST	654+06	61.8' LT		LD	SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST	24	× 30
E3-17a	RIGHT TURN ONLY	MOUNTED ON SIGNAL FOST	034+00	61.8 LI		WB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	30"	x 36"
E3-17b	FOLDED STOP SIGN		+			WB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		x 30"
E3-170		DOST MOUNTED (CONCRETE MEDIANI)	654+14	5.6'	RT	WD		30 .	X 30
E3-16	(SHARED POST)	POST MOUNTED (CONCRETE MEDIAN)	004+14	3.0	ΚI	EB	SIGN PANEL ASSEMBLY TO BE RELOCATED SIGN PANEL TO BE RELOCATED WITH ASSEMBLY	24"	x 30"
	KEEP RIGHT						SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		
E3-18b	LEFT TURN ONLY	DOST MOUNTED (CROUND)	654160	27 41	рт		SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		x 30"
E3-19	LANE ENDS	POST MOUNTED (GROUND)	654+62	37.1'	RT	EB	SIGN PANEL ASSEMBLY TO BE REMOVED		x 36"
E3-20	DIVIDED HIGHWAY ENDS	POST MOUNTED (GROUND)	656+61	38.1'	RT	EB	SIGN PANEL ASSEMBLY TO BE REMOVED		x 36"
E3-21	RIGHT TURN LANE	POST MOUNTED (GROUND)	657+13	51.2'	LT	WB	SIGN PANEL ASSEMBLY TO BE RELOCATED		x 24"
E3-22	SPEED LIMIT 40	CIRCULAR POST MOUNTED (GROUND)	658+16	49.7'	LT	WB	SIGN PANEL ASSEMBLY TO BE REMOVED		x 36"
E3-23	KEEP RIGHT	CIRCULAR POST MOUNTED (LANDSCAPED MEDIAN)	658+19	0.8'	RT	WB	SIGN PANEL ASSEMBLY TO BE REMOVED		x 30"
E3-24	SPEED LIMIT 35	POST MOUNTED (GROUND)	658+28	38.2'	RT	EB	SIGN PANEL ASSEMBLY TO BE REMOVED		x 36"
E3-25	SCHOOL CROSSING	POST MOUNTED (GROUND)	660+31	37.8'	RT	EB	SIGN PANEL ASSEMBLY TO BE RELOCATED	36"	x 36"
	STA 661+00 TO STA 672+00)	1	T		1		T	T	
E4-1	STOP SIGN	MOUNTED ON METAL GATE	661+54	79.9'	LT	NB	SIGN TO REMAIN		x 30"
E4-2	SPEED LIMIT 35	POST MOUNTED (GROUND)	664+02	46.5'	LT	WB	SIGN PANEL ASSEMBLY TO BE REMOVED		x 36"
E4-3	LUTHERAN CHURCH OF THE ASCENSION	NONE - SIGN IS A STONE BLOCK	664+34	106.9'	RT	SB	SIGN TO REMAIN	197"	x 37"
E4-4	(SHARED POST)	MOUNTED ON SIGNAL POST	664+60	46.6'	LT		SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST		
E4-4a	SUNSET RIDGE RD					WB	SIGN PANEL TO BE REMOVED		x 18"
E4-4b	NO TURN ON RED					WB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		x 24"
E4-4c	ON SCHOOL DAY WHEN CHILDREN ARE PRESENT					WB	SIGN PANEL TO BE RELOCATED WITH ASSEMBLY		x 12"
E4-5 E4-6	PACE BUS STOP	POST MOUNTED (GROUND)	664+66	30.8'	RT	EB	SIGN PANEL ASSEMBLY TO BE RELOCATED		x 18"
	FOLDED STOP SIGN	MOUNTED ON SIGNAL POST	664+74	28.3'	RT	EB	SIGN PANEL TO BE RELOCATED ON NEW SIGNAL POST	36"	x 36"

FILE NAME =	USER NAME = BAWitort	DESIGNED	-	JLV	REVISED	-
g:\ch11\0158\road\Sheets\D160T35-SHT-SIG	N-SCHØ2.dgn	DRAWN	-	MTS	REVISED	-
	PLOT SCALE = 40.000 '/ in.	CHECKED	-	RCB	REVISED	-
	PLOT DATE = 11/1/2012	DATE	-	10/31/2012	REVISED	-

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

	SIGN SCHEDULE			.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				305	(1920.01,1518,2022&1922.4B)R	COOK	919	290
						CONTRACT	NO. 60	T35
	SCALE: N.T.S	SHEET NO. 290 OF 919 SHEETS	FE	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

NOTE:

- 1. SIGN SHALL BE RE-ERECTED ACCORDING TO ARTICLE 107.25 OF THE STANDARD SPECIFICATION (PROTECTION AND RESTORATION OF TRAFFIC SIGNS). ADDITIONAL SIGNS THAT HAVE NOT BEEN SURVEYED BUT ARE OBSCURED BY CONSTRUCTION OPERATIONS SHALL ALSO BE RE-ERECTED ACCORDING TO ARTICLE 107.25.
- 2. ALL EXISTING PRIVATE SIGNS WITHIN THE STATE ROW THAT INTERFERE WITH CONSTRUCTION OPERATIONS WILL BE REMOVED AND REPLACED BY OTHERS. THE CONTRACTOR SHALL NOTIFY THE OWNERS PRIOR TO THE START OF CONSTRUCTION.
- 3. EXISTING SIGN PANEL AND ASSEMBLY TO BE REMOVED SHALL BE DELIVERED TO AN IDOT MAINTENANCE YARD SPECIFIED BY THE ENGINEER.