SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER-CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9		
	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	315				315
Δ	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	71	71			
	X6025600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	1	1			
	X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1		1		
	X8600105	MASTER CONTROLLER (SPECIAL)	EACH	1		1		
	X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1		
	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	2232			2232	
Δ	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	32	32			
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	154.20	154.20	Δ1		
	Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1			1	
	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1		
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	10	10			
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3			

Δ NON-PARTICIPATING (100% STATE)

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER-CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021

Δ1 Rev. 1-3-13

* SPECIALTY ITEMS

FILE NAME =	USER NAME = hamdanah	DESIGNED -	REVISED -
c:\dot_workspace\hamdanah\d0286304\P114712-sht-typical.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / In.	CHECKED -	REVISED -
	PLOT DATE = 10/23/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BURNHAM AVE AT RIVER OAKS DR
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2943	3162A-N-1	COOK	42	7
		CONTRACT NO. 60T47		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

P114712-sht-typical.dgn 10/23/2012 11:29:12 AM User=hamdanah