

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6					60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2					
40600300	AGGREGATE (PRIME COAT)	TON	28	28					60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11					60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	12	12					
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	285	285					60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	30	30					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 12 (MODIFIED)	FOOT	3500	3500					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	14	14					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	575	575					67100100	MOBILIZATION	L SUM	1	1					
42001300	PROTECTIVE COAT	SO YD	780	780					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	5250	5250					70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	6500	6500					70300100	SHORT TERM PAVEMENT MARKING	FOOT	400	400					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3500	3500				X	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	100	100					
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	100	100				Y	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3530	3530					
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	100	100				X	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	276	276					
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	500	500				X	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	20	20					
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	16	16				X	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	100					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80	80					

URBAN
100%
STATE

URBAN
100%
STATE

*Specialty Items

FILE NAME:	USER NAME: <i>Perkins</i>	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE. 846	SECTION 4RS-B	COUNTY WILL	TOTAL SHEETS 14	SHEET NO. 3
CONTRACT NO. 60V16	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT												