

URBAN

URBAN

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT			0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	19	19					
25200110	SODDING, SALT TOLERANT	SO YD	19	19					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	45					
40600300	AGGREGATE (PRIME COAT)	TON	222	222					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	84	84					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3875	3875					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1538	1538					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5918	5918					
42001300	PROTECTIVE COAT	SO YD	22	22					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	14988	14988					
44022029	PARTIAL DEPTH REMOVAL 3"	SO YD	2358	2358					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	416	416					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	250	250					

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT			0005				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	167	167					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	671	671					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2391	2391					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	292	292					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38981	38981					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1038	1038					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1341	1341					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70					

* SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN	REVISED			350	1101W-EXT-RRRS	WILL	31	3			
		CHECKED	REVISED			F.A.P. 350/ IL. 50 (CICERO AVE.)-STEEGER RD. TO GOVERNORS HWY.			CONTRACT NO. 60V65				
		DATE	REVISED			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				