

| ITEM NO. | SPECIALTY ITEM | SP | CODE NUMBER | ITEM | UNIT | TOTAL QUANTITY | RECONSTRUCTION, CAPACITY ADDED | BRIDGE, NEW CONSTRUCTION | SAFETY (TRAFFIC SIGNALS, LIGHTING, SIDEWALKS, EVPS) |
|----------|----------------|----|-------------|-------------------------------------|-------|----------------|--------------------------------|--------------------------|---|
| | | | | | | | 0003 | 0008 | 0021 |
| | | | | | | | 100% STATE | 100% STATE | |
| 15 | | | 28000305 | TEMPORARY DITCH CHECKS | FOOT | 2,328 | 1,368 | 960 | |
| 16 | | | 28000400 | PERIMETER EROSION BARRIER | FOOT | 14,130 | 6,102 | 8,028 | |
| 17 | | | 28000500 | INLET AND PIPE PROTECTION | EACH | 159 | 156 | 3 | |
| 18 | | | 28000510 | INLET FILTERS | EACH | 156 | 156 | | |
| 19 | | | 28100107 | STONE RIPRAP, CLASS A4 | SO YD | 443 | | 443 | |
| 20 | | | 28100109 | STONE RIPRAP, CLASS A5 | SO YD | 42 | | 42 | |
| 21 | | | 28200200 | FILTER FABRIC | SO YD | 647 | | 647 | |
| 22 | | | 44000100 | PAVEMENT REMOVAL | SO YD | 3,624 | 3,624 | | |
| 23 | | | 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 2535 | 2535 | | |
| 24 | | | 44000600 | SIDEWALK REMOVAL | SO FT | 3439 | 3439 | | |
| 25 | | | 44003100 | MEDIAN REMOVAL | SO FT | 673 | 673 | | |
| 26 | | | 44201819 | CLASS D PATCHES, TYPE III, 14 INCH | SO YD | 20 | 20 | | |
| 27 | | | 44201821 | CLASS D PATCHES, TYPE IV, 14 INCH | SO YD | 33 | 33 | | |
| 28 | | | 50100100 | REMOVAL OF EXISTING STRUCTURES | EACH | 1 | | 1 | |



USER NAME - user
 PLOT SCALE - #SCALE#
 PLOT DATE - 11/2/2012

DESIGNED - MPK
 DRAWN - ML
 CHECKED - LGP
 DATE - 11-02-2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL ROUTE 19 (IRVING PARK RD.) AND YORK RD.
 SCALE: NTS SHEET NO. 2 OF 13 SHEETS STA. TO STA.

F.A.J. RTE. 132I SECTION 32VB COUNTY DUPAGE TOTAL SHEETS 388 SHEET NO. 8
 ILLINOIS FED. AID PROJECT CONTRACT NO. 60W01

Rev.