

ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	RECONSTRUCTION, CAPACITY ADDED	BRIDGE, NEW CONSTRUCTION	SAFETY (TRAFFIC SIGNALS, LIGHTING, SIDEWALKS, EVPS)
							0003 100% STATE	0008 100% STATE	0021
43			54002020	EXPANSION BOLTS 3/4 INCH	EACH	66		66	
44			54003000	CONCRETE BOX CULVERTS	CU YD	76.4		76.4	
45			542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	38		38	
46			542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	40		40	
47			542D3391	PIPE CULVERTS, CLASS D, TYPE 5 36"	FOOT	75		75	
			54261330	CONCRETE END SECTION, STANDARD 542D01, 30", 1:3	EACH	2		2	
48			54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2		2	
49			54213879	STEEL END SECTIONS 24"	EACH	2		2	
50			54213891	STEEL END SECTIONS 36"	EACH	2		2	
			54260311	TRAVERSABLE PIPE GRATE	FOOT	23		23	
51			54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1		1	
52			550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	251	251		
53			58700300	CONCRETE SEALER	SO FT	6,174		6,174	
54			59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	2,484		2,484	
55			59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	895.6	139.0	756.6	
56			60235800	INLETS, TYPE A, TYPE 4 FRAME AND GRATE	EACH	4	4		



USER NAME : user	DESIGNED - MPK	REVISED -
PLOT SCALE : *SCALE*	DRAWN - ML	REVISED -
PLOT DATE : 11/2/2012	CHECKED - LGP	REVISED -
	DATE - 11-02-2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
IL ROUTE 19 (IRVING PARK RD.) AND YORK RD.			
SCALE: NTS	SHEET NO. 4 OF 13 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	32VB	DUPAGE	388	10
CONTRACT NO. 60W01				
ILLINOIS FED. AID PROJECT				

Rev.