

ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	RECONSTRUCTION,	BRIDGE,	SAFETY (TRAFFIC
							CAPACITY ADDED	NEW CONSTRUCTION	SIGNALS, LIGHTING, SIDEWALKS, EVPS)
							0003	0008	0021
							100% STATE	100% STATE	
99	+		81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	1,540			1,540
100	+		81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	40			40
101	+		81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE-USE) 3-1/C NO. 6	FOOT	354			354
102	+		81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	578			578
103	+		82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	7			7
104	+		82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8			8
105	+		82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1			1
106	+		83057012	LIGHT POLE, WOOD, 30 FOOT, CLASS 5	EACH	1			1
107	+		83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	7			7
108	+		84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1
109	+		84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1
110	+		84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1
111	+		85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3			3
112	+		85000400	MAINTENANCE OF TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1



USER NAME = user	DESIGNED - MPK	REVISED -
PLOT SCALE = #SCALE#	DRAWN - ML	REVISED -
PLOT DATE = 11/2/2012	CHECKED - LGP	REVISED -
	DATE - 11-02-2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 19 (IRVING PARK RD.) AND YORK RD.

F.A.D. RTE. 1321	SECTION 32VB	COUNTY	TOTAL SHEETS 388	SHEET NO. 14
SCALE: NTS	SHEET NO. 8 OF 13 SHEETS	STA. TO STA.	CONTRACT NO. 60W01	
(ILLINOIS) FED. AID PROJECT				