

SCHEDULE OF EARTHWORK								
LOCATION	EARTH EXCAVATION	EXCAVATION AVAILABLE	EMBANKMENT VOLUME NEEDED	BALANCE PER STAGE WASTE (+) NEED (-)	FURNISHED EXCAVATION	FURNISHED EXCAVATION, SPECIAL	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUB-BALLAST
	CU YD	ADJUSTED FOR SHRINKAGE CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
IL 19 - STAGE 1 - STA. 397+25 TO STA. 408+50	3,220	2,737	74	2,663	0	0	0	0
IL 19 - STAGE 1A - STA. 397+25 TO STA. 408+50	145	123	34	89	0	0	0	0
IL 19 - STAGE 2 - STA. 397+25 TO STA. 408+50	218	185	61	124	0	0	0	0
IL 19 - STAGE 3 - STA. 397+25 TO STA. 408+50	1,090	927	51	876	0	0	0	0
IL 19 - STAGE 4 - STA. 397+25 TO STA. 408+50	742	631	18	613	0	0	0	0
IL 19 - STAGE 5 - STA. 397+25 TO STA. 408+50	0	0	0	0	0	0	0	0
SUBTOTAL ROADWAY	5,415	4,603	238	4,365	0	0	0	0
CANADIAN PACIFIC RAILWAY STAGE RR-1	1,261	1,072	96,232	-95,160	95,160	0	13,963	6,687
CANADIAN PACIFIC RAILWAY STAGE RR-1A	120	102	1,200	-1,098	0	1,098	0	935
CANADIAN PACIFIC RAILWAY STAGE RR-2	108	92	4,116	-4,024	4,024	0	640	359
CANADIAN PACIFIC RAILWAY STAGE RR-2A	138	118	1,291	-1,173	0	1,173	0	1,016
CANADIAN PACIFIC RAILWAY STAGE RR-3	3,422	2,909	11,131	-8,222	8,222	0	2,325	772
SUBTOTAL CANADIAN PACIFIC RAILWAY	5,050	4,293	113,971	-109,678	107,410	2,275	16,930	9,770
PROJECT TOTAL	10,465	8,896	114,209	-105,313	107,410	2,275	16,930	9,770
(15% SHRINKAGE FACTOR)								



USER NAME = user	DESIGNED - MPK	REVISED -
	DRAWN - ML	REVISED -
PLOT SCALE = #SCALE#	CHECKED - LGP	REVISED -
PLOT DATE = 11/26/2012	DATE - 11-20-2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES</b>			
<b>IL ROUTE 19 (IRVING PARK RD.) AND YORK RD.</b>			
SCALE: NTS	SHEET NO. 1 OF 12 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	32VB	DUPAGE	388	23
CONTRACT NO. 60W01				
ILLINOIS FED. AID PROJECT				