

EROSION CONTROL BLANKET					SQ YD
	STA.	STA	OFFSET	AREA (SQ FT)	AREA (SQ YD)
CANADIAN PACIFIC RAILWAY					
STAGE RR-1					
CP RWY	10271+95.48	10286+00.00	RT	24,165	2,685
CP RWY	10286+00.00	10298+00.00	RT	29,491	3,277
CP RWY	10289+67.20	10294+00.00	LT	12,685	1,409
CP RWY	10296+56.78	10298+00.00	LT	5,537	615
CP RWY	10298+00.00	10298+43.82	RT	665	74
CP RWY	10298+00.00	10298+45.32	LT	1,670	186
CP RWY	10300+16.32	10313+00.00	RT	50,619	5,624
CP RWY	10313+00.00	10327+12.40	RT	20,940	2,327
				SUB-TOTAL:	16,197
STAGE RR-2					
CP RWY	10292+00.00	10294+52.45	LT	7,528	836
CP RWY	10295+84.52	10298+00.00	LT	6,148	683
CP RWY	10298+00.00	10298+45.32	LT	653	73
				SUB-TOTAL:	1,592
STAGE RR-3					
CP RWY	10283+07.02	10286+00.00	LT	4,825	536
CP RWY	10286+00.00	10298+00.00	LT	32,537	3,615
CP RWY	10298+00.00	10298+45.32	LT	726	81
CP RWY	10300+16.54	10313+00.00	LT	66,035	7,337
CP RWY	10302+63.49	10303+67.65	RT	3,043	338
CP RWY	10313+00.00	10327+12.44	LT	30,363	3,374
				SUB-TOTAL:	15,281
				CANADIAN PACIFIC RAILWAY SUBTOTAL:	33,070
IL-19					
STAGE 5					
IL-19	397+45.79	398+09.58	RT	2,622	291
IL-19	397+38.01	398+01.16	LT	3,096	344
IL-19	398+31.29	408+56.25	RT	60,514	6,724
IL-19	398+16.26	406+00.00	LT	24,176	2,686
				SUBTOTAL:	10,045
				IL-19 SUBTOTAL:	10,045
				PROJECT TOTAL:	43,115

TURF REINFORCEMENT MAT					SQ YD	
	STA.	TO	STA.	LT/RT	AREA (SQ FT)	AREA (SQ YD)
STAGE RR-1						
CP RWY	10271+95.48		10286+00.00	RT	24,165	2,685
	10286+00.00		10298+00.00	RT	29,491	3,277
	10289+36.96		10294+03.63	LT	8,377	931
	10296+56.78		10298+00.00	LT	3,653	406
	10298+00.00		10298+45.32	RT	682	76
	10298+00.00		10298+45.32	LT	1,269	141
	10300+16.32		10313+00.00	RT	50,619	5,624
	10313+00.00		10327+12.44	RT	20,940	2,327
				SUB-TOTAL:		15,466
STAGE RR-2						
CP RWY	10294+02.17		10294+82.34	LT	3,473	386
	10295+84.50		10296+65.02	LT	3,582	398
				SUB-TOTAL:		784
STAGE RR-3						
CP RWY	10282+91.19		10286+00.00	LT	4,825	536
	10286+00.00		10292+00.00	LT	10,243	1,138
	10294+52.45		10296+24.03	LT	3,744	416
	10300+16.32		10313+00.00	LT	46,787	5,199
	10302+63.49		10303+67.65	RT	3,043	338
	10313+00.00		10327+12.44	LT	26,281	2,920
				SUB-TOTAL:		10,547
				TOTAL:		26,797