

STONE RIPRAP, CLASS A4						SQ YD
LOCATION	STATION	TO	STATION	ITEM	AREA (SQ YD)	
CPR BRIDGE					16	
CPR STAGE RR-1	10303+24.24	-	10303+64.59	CPR TEMP CULVERT OUTLET	67	
	10321+70.00	-	10321+80.00	24" CULVERT INLET	12	
	10322+20.00	-	10322+40.00	24" CULVERT OUTLET	45	
CPR STAGE RR-2				NONE		
CPR STAGE RR-3						
	10283+95.00	-	10284+05.00	36" CULVERT INLET	12	
	10303+04.00	-	10303+42.18	CPR PROP. CULVERT OUTLET	230	
	20326+34.48	-	20326+34.48	30" CULVERT INLET	12	
	20326+72.15	-	20326+94.15	30" CULVERT OUTLET	49	
TOTAL					443	

FILTER FABRIC				SQ YD
LOCATION	STATION	ITEM	AREA (SQ YD)	
CPR BRIDGE			16	
CPR STAGE RR-1	10303+46.06	TEMPORARY CULVERT OUTLET	93	
	10321+80.00	24" TEMP CULV. INLET	22	
	10322+20.00	24" TEMP CULV. OUTLET	64	
CPR STAGE RR-2	10284+00.00	36" CULVERT OUTLET	61	
CPR STAGE RR-3	10284+00.00	36" CULVERT INLET	22	
	10303+05.32	PROPOSED CULVERT OUTLET	277	
	10326+34.48	30" CULVERT INLET	22	
	10326+72.14	30" CULVERT OUTLET	70	
TOTAL			647	

STONE RIPRAP, CLASS A5						SQ YD
LOCATION	STATION	TO	STATION	ITEM	AREA (SQ YD)	
CPR STAGE RR-2	10283+87.00	-	10284+13.00	36" CULVERT OUTLET	42	
TOTAL					42	

PIPE CULVERT REMOVAL				FOOT
STATION	TO	STATION	LENGTH (FT)	
CANADIAN PACIFIC RAILWAY (STAGE RR-3)				
10321+80 LT	-	10322+20 LT	40	
IL ROUTE 19 (IRVING PARK RD.)				
397+30 RT	-	397+90 RT	58	
TOTAL:			98	



USER NAME = user	DESIGNED - MPK	REVISED -
	DRAWN - ML	REVISED -
PLOT SCALE = *SCALE*	CHECKED - LGP	REVISED -
PLOT DATE = 11/2/2012	DATE - 11-02-2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
IL ROUTE 19 (IRVING PARK RD.) AND YORK RD.**

SCALE: NTS SHEET NO. 9 OF 12 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	32VB	DUPAGE	388	31
CONTRACT NO. 60W01				
ILLINOIS FED. AID PROJECT				