

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	FUNDING BREAKDOWN		LOCATION OF WORK				
		UNIT	TOTAL	U.S. ROUTE 14	DAVIS STREET / ARTHUR AVENUE	LIGHTING	U.S. 14/DAVIS ST. @ ARTHUR AVENUE	EVP
		CONSTRUCTION TYPE CODE						
				0004	0021	0021	0021	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	18,175	10,300	7,875			
42400800	DETECTABLE WARNINGS	SQ FT	550	250	300			
44000100	PAVEMENT REMOVAL	SQ YD	8,162	1,502	6,660			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	940	295	645			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10,151	7,337	2,814			
44000600	SIDEWALK REMOVAL	SQ FT	17,954	10,405	7,549			
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	230	230				
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	130	130				
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	434	434				
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	217	217				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6,916	6,916				
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	2		2			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	686	663	23			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	5	5				
55100300	STORM SEWER REMOVAL 8"	FOOT	45	45				
55100400	STORM SEWER REMOVAL 10"	FOOT	8		8			
55100500	STORM SEWER REMOVAL 12"	FOOT	234	198	36			
55100700	STORM SEWER REMOVAL 15"	FOOT	10	10				
56400100	^ * FIRE HYDRANTS TO BE MOVED	EACH	2	1	1			
60107600	PIPE UNDERDRAINS 4"	FOOT	2,513	2,127	386			
60201330	CATCH BASINS, TYPE A, 4-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	12	10	2			
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	2	2				
60219530	MANHOLES, TYPE A, 4-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	2	2				
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1				
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	16	15	1			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	9	6	3			
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1		1			
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60255500	MANHOLES TO BE ADJUSTED	EACH	6	5	1			
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME OPEN LID	EACH	1	1				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	1	1			
60260100	INLETS TO BE ADJUSTED	EACH	3	2	1			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	11	9	2			
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1	1				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	9	8	1			
60500040	REMOVING MANHOLES	EACH	1	1				

* DENOTES SPECIAL PROVISION
 ^ DENOTES SPECIALTY ITEM
 ^# DENOTES CONSTRUCTION TYPE CODE Y080
 # DENOTES NON-PARTICIPATING ITEM

PLAN SURVEYED BY DATE
 PLOTTED BY DATE
 CHECKED BY DATE
 RTM OF WAY CHECKED
 RTM FILE NAME

PROFILE SURVEYED BY DATE
 CHECKED BY DATE
 RTM NOTED
 STRUCTURE NOTATIONS CPWD



USER NAME = #USER#
 DESIGNED - RTM
 DRAWN - JRR
 CHECKED - RTM
 DATE - 10/22/12

REVISED - 11/07/12
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO 2 OF 6 SHEETS

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3512	02-00177-00 WR	COOK	142	4
PROJECT NO. M-8003(426)			CONTRACT NO. 63514	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				