

# SUMMARY OF QUANTITIES

CODE NO.		PAY ITEM	FUNDING BREAKDOWN		LOCATION OF WORK				CONSTRUCTION TYPE CODE				
			UNIT	TOTAL	U.S. ROUTE 14	DAVIS STREET / ARTHUR AVENUE	LIGHTING	U.S. 14/DAVIS ST. @ ARTHUR AVENUE	EVP	0004	0021	0021	0021
81028210	^	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	448						240	208		
81028220	^	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	127							127		
81028240	^	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,553						950	603		
81028260	^	UNDERGROUND CONDUIT, GALVANIZED STEEL, 6" DIA.	FOOT	88							88		
81028350	^	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	4,050					4,050				
81400100	^	HANDHOLE	EACH	6							6		
81400200	^	HEAVY-DUTY HANDHOLE	EACH	2							2		
81400300	^	DOUBLE HANDHOLE	EACH	2							2		
81702120	^	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	5,000					5,000				
81702140	^	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	14,500					14,500				
81702400	^	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	200					200				
81800190	^	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	3,400					3,400				
82102250	^	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	15					15				
82102400	^	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	22					22				
82500360	^	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1					1				
83007600	^	LIGHT POLE, ALUMINUM, 35 FT. M.H., 15 FT. MAST ARM	EACH	11					11				
83050440	^	LIGHT POLE, ALUMINUM, 35 FT. M.H., 2-15 FT. MAST ARMS	EACH	2					2				
83050810	^	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	18					18				
83050910	^	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-15 FT. MAST ARMS	EACH	2					2				
83057295	^	LIGHT POLE, WOOD, 50 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	12					12				
83057355	^	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	22					22				
83600200	^	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	424					424				
84100110	^	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	34					34				
84200500	^	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	20					20				
84200804	^	REMOVAL OF POLE FOUNDATION	EACH	20					20				
84500110	^	REMOVAL OF LIGHTING CONTROLLER	EACH	1					1				
84500120	^	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1					1				
84500130	^	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1					1				
85700310	^	RAILROAD, FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1							1		
87301215	^	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	917							917		
87301225	^	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,878							1,878		
87301245	^	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5,458							5,458		
87301305	^	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2,441							2,441		
87301750	^	ELECTRIC CABLE IN CONDUIT, RAILROAD, NO. 14 3C	FOOT	40							40		
87301805	^	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	38							38		
87301900	^	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,216							1,216		
87502440	^	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1							1		

\* DENOTES SPECIAL PROVISION  
^ DENOTES SPECIALTY ITEM  
^^ DENOTES CONSTRUCTION TYPE CODE Y080  
# DENOTES NON-PARTICIPATING ITEM

PLAN	DATE
BY	
SURVEYED	
PLOTTED	
PRINTED	
FILED	
NO. _____	

PROFILE	DATE
BY	
SURVEYED	
PLOTTED	
PRINTED	
FILED	
NO. _____	



USER NAME = #USER#  
PLOT SCALE = #SCALE#  
PLOT DATE = #DATE#

DESIGNED - RTM  
DRAWN - JRR  
CHECKED - RTM  
DATE - 10/22/12

REVISED - 11/07/12  
REVISED - 11/29/12  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

## SUMMARY OF QUANTITIES

SHEET NO 4 OF 6 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3512	02-00177-00 WR	COOK	142	6
PROJECT NO. M-8003(426)			CONTRACT NO. 63514	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				