

SCHEDULE OF QUANTITIES

4 SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
U.S. Route 14 / Davis Street / Arthur Avenue													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	AGGREGATE SUBGRADE IMPROVEMENT	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	AGGREGATE SUBGRADE IMPROVEMENT	FURNISHED EXCAVATION	EARTH EXCAVATION (CUT)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT	FURNISHED EXCAVATION (FILL)
										(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
547+00		0	0	0	0								
547+50	50	11	0	0	3	6	0	0	2	275	0	0	75
548+00	50	19	0	0	3	15	0	0	3	750	0	0	150
548+50	50	27	0	0	3	23	0	0	3	1,150	0	0	150
549+00	50	28	0	0	4	28	0	0	4	1,375	0	0	175
549+50	50	31	0	0	5	30	0	0	5	1,475	0	0	225
550+00	50	33	0	0	4	32	0	0	5	1,600	0	0	225
550+50	50	32	0	0	6	33	0	0	5	1,625	0	0	250
551+00	50	31	0	0	7	32	0	0	7	1,575	0	0	325
551+50	50	30	0	0	9	31	0	0	8	1,525	0	0	400
552+00	50	30	0	1	8	30	0	1	9	1,500	0	25	425
552+50	50	31	0	0	6	31	0	1	7	1,525	0	25	350
553+00	50	34	9	9	6	33	5	5	6	1,625	225	225	300
553+50	50	31	8	8	4	33	9	9	5	1,625	425	425	250
554+00	50	32	8	8	4	32	8	8	4	1,575	400	400	200
554+50	50	54	18	18	3	43	13	13	4	2,150	650	650	175
555+00	50	4	2	2	1	29	10	10	2	1,450	500	500	100
555+50	50	96	24	24	1	50	13	13	1	2,500	650	650	50
556+00	50	14	5	5	3	55	15	15	2	2,750	725	725	100
556+50	50	12	0	0	3	13	3	3	3	650	125	125	150
557+00	50	10	0	0	3	11	0	0	3	550	0	0	150
557+50	50	9	0	0	3	10	0	0	3	475	0	0	150
558+00	50	9	0	0	3	9	0	0	3	450	0	0	150
558+50	50	5	0	0	1	7	0	0	2	350	0	0	100
559+00	50	15	14	14	3	10	7	7	2	500	350	350	100
559+50	50	22	6	6	3	19	10	10	3	925	500	500	150
560+00	50	30	8	8	4	26	7	7	4	1,300	350	350	175
560+50	50	37	10	10	3	34	9	9	4	1,675	450	450	175
561+00	50	35	9	9	3	36	10	10	3	1,800	475	475	150
561+50	50	31	8	8	4	33	9	9	4	1,650	425	425	175
562+00	50	27	7	7	3	29	8	8	4	1,450	375	375	175
562+50	50	22	6	6	3	25	7	7	3	1,225	325	325	150
563+00	50	34	17	17	1	28	12	12	2	1,400	575	575	100
563+50	50	18	5	5	3	25	11	11	2	1,250	550	550	100
564+00	50	12	3	3	3	14	4	4	3	700	200	200	150
564+50	25	12	0	0	3	12	2	2	3	600	75	75	150
564+75		0	0	0	0	6	0	0	2	150	0	0	38
PROJECT OMISSION		PROJECT OMISSION STATION 564+66 TO STATION 574+12				PROJECT OMISSION STATION 564+66 TO STATION 574+12				PROJECT OMISSION STATION 564+66 TO STATION 574+12			

PLAN	DATE
BY	
REVISIONS	
NO. 1	
NO. 2	
NO. 3	
NO. 4	
NO. 5	
NO. 6	
NO. 7	
NO. 8	
NO. 9	
NO. 10	

PROFILE	DATE
BY	
REVISIONS	
NO. 1	
NO. 2	
NO. 3	
NO. 4	
NO. 5	
NO. 6	
NO. 7	
NO. 8	
NO. 9	
NO. 10	



USER NAME = #USER#
 PLOT SCALE = #SCALE#
 PLOT DATE = #DATE#

DESIGNED - RTM
 DRAWN - JRR
 CHECKED - RTM
 DATE - 10/22/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO 2 OF 6 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3512	02-00177-00 WR	COOK	142	12
PROJECT NO. M-8003(426)		CONTRACT NO. 63514		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				