SCHEDULE OF QUANTITIES

5	SCHEDULE OF HOT-MIX ASPHALT DRVEWAY PAVEMENT					
STATION		AREA 2" THICK	AREA 3" THICK	AREA 8" THICK	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (40603340)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (40603085)
FROM	TO	SQ YD	SQ YD	SQ YD	TON	TON
547+04	551+00	0	0	0	0	0
551+00	556+50	0	0	0	0	0
556+50	562+00	0	0	0	0	0
562+00	564+66	0	0	0	0	0
574+12	577+00	0	0	0	0	0
577+00	582+50	0	0	0	0	0
582+50	588+00	0	0	0	0	0
588+00	591+09	0	0	0	0	0
U.S. 14 SUBTOTAL		0	0	0	0	0
13+52	18+75	0	0	0	0	0
18+75	22+17	0	160	0	27	0
DAVIS STREET		0	160	0	0	0
904+75	908+00	123	0	123	14	57
908+00	910+00	200	0	200	22	92
ARTHUR AVENUE		323	0	323	36	149
PROJECT TOTAL					63	149
					*UNIT WEIGHT = 112 LB/SQ YD INCH	*UNIT WEIGHT = 115 LB/SQ YD INCH

6	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT						
STATION		AREA	THICKNESS	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6 INCH (42300200)	AREA	THICKNESS	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8 INCH (42300400)
STATION	LT/RT	(SQ. FT.)	(IN.)	(SQ. YD.)	(SQ. FT.)	(IN.)	(SQ. YD.)
577+50	LT			0	190	8.0	21
578+00	LT			0	240	8.0	27
580+65	LT			0	150	8.0	17
584+60	LT			0	190	8.0	21
589+42	LT			0	270	8.0	30
		U.S. ROUTE 14 SUBTOTAL		0			116
905+00	RT			0	130	8.0	14
905+33	RT			0	140	8.0	16
905+50	LT			0	270	8.0	30
905+85	LT			0	310	8.0	34
906+31	RT			0	165	8.0	18
906+89	LT			0	485	8.0	54
906+89	RT			0	210	8.0	23
907+66	LT			0	370	8.0	41
908+13	RT			0	270	8.0	30
908+84	LT			0	520	8.0	58
909+36	RT			0	190	8.0	21
909+75	LT			0	440	8.0	49
910+15	LT			0	350	8.0	39
		ARTHUR AVENUE SUBTOTAL		0			428
14+18	RT	365	6.0	41			0
14+59	RT	400	6.0	44			0
15+04	RT	310	6.0	34			0
15+89	RT	290	6.0	32			0
16+69	RT	220	6.0	24			0
18+40	RT			0	240	8.0	27
		DAVIS STREET SUBTOTAL		176			27
		PROJECT TOTAL		176	PROJECT TOTAL		570

7	SCHEDULE OF PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (42400200)	
STATION		
FROM	TO	SQ FT
547+04	551+00	625
551+00	556+50	2,625
556+50	562+00	2,825
562+00	564+66	350
574+12	577+00	875
577+00	582+50	1,675
582+50	588+00	350
588+00	591+09	975
U.S. 14 SUBTOTAL		10,300
13+52	18+75	2,675
18+75	22+17	1,800
DAVIS STREET SUBTOTAL		4,475
904+75	908+00	2,875
908+00	910+00	525
ARTHUR AVENUE SUBTOTAL		3,400
	PROJECT TOTAL	18,175

8	SCHEDULE OF REMOVAL ITEMS						
STATION		HOT-MIX ASPHALT SURFACE REMOVAL BUTT-JOINT (40600982)	PAVEMENT REMOVAL (44000100)	DRIVEWAY PAVEMENT REMOVAL (44000200)	COMBINATION CURB AND GUTTER REMOVAL (44000500)	SIDEWALK REMOVAL (44000600)	HOT-MIX ASPHALT SURFACE REMOVAL VARIABLE DEPTH (X4401198)	CONCRETE MEDIAN REMOVAL (X4403300)
FROM	TO	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)	(SQ FT)	(SQ YD)	(SQ FT)
547+04	551+00	28	0	0	792	680	2,269	0
551+00	556+50	9	529	0	1,148	2,625	3,408	1,377
556+50	562+00	14	23	0	1,118	2,825	3,797	0
562+00	564+66	51	52	0	583	350	1,768	0
574+12	577+00	40	42	0	613	921	1,849	0
577+00	582+50	30	500	42	1,261	1,675	3,794	0
582+50	588+00	16	350	209	1,164	350	3,018	0
588+00	591+09	28	6	44	658	979	1,761	0
U.S. 14 SUBTOTAL		216	1,502	295	7,337	10,405	21,684	1,377
13+52	18+75	0	2,406	124	1,032	2,832	0	50
18+75	22+17	0	2,140	26	722	1,747	0	0
DAVIS STREET		0	4,547	150	1,754	4,379	0	50
904+75	908+00	0	1,842	260	650	1,818	0	0
908+00	910+00	0	270	235	410	1,352	0	0
ARTHUR AVENUE		0	2,113	495	1,060	3,170	0	0
PROJECT TOTAL		216	8,162	940	10,151	17,954	21,684	1,427

9	SCHEDULE OF STORM SEWERS AND TRENCH BACKFILL									
STATION			550A0040	550A0050	550A0070	X5504200	Z0056606	Z0056608	Z0056610	Z0800150
FROM	TO	PIPE #	SS, CL A, TY 1,10"	SS, CL A, TY 1,12"	SS, CL A, TY 1,15"	D I STORM SEWER 12	STORM SEW WM REQ 10	STORM SEW WM REQ 12	STORM SEW WM REQ 15	TRNCH BKFILL
			(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(CU YD)
547+04	551+00	1		167						40
		2		57				15		30
551+00	556+50	3					10			2
		4					20			5
		5		32						5
556+50	562+00	6		126						29
		7			2					2
		8							4	2
		9			3					3
		10		5						3
562+00	564+66	11		7						3
		12		107						25
		13		67						30
574+12	577+00	14		4						2
		15		42				10		12
577+00	582+50	16								2
		17								2
		18				5				5
		19				5				2
		20						3		2
582+50	588+00	21		49						7
		22				5				2
		23				5				2
		24						222		55
588+00	591+09	25						4		2
		26						5		2
		27				5				2
		28				4				2
		29				2				2
13+52	18+75	30		23				13		5
908+00	910+00	31	2							2

PLAN
SURVEYED
PLOTTED
DRAWN / CHECKED
RT.-OF-WAY CHECKED
CADD FILE NAME
NOTE BOOK
NOS.
BY
DATE

PROFILE
SURVEYED
PLOTTED
DRAWN / CHECKED
R.M. NOTED
STRUCTURE NOTATIONS CHKD
NOTE BOOK
NOS.
BY
DATE

CIVILTECH

USER NAME = @USER@	DESIGNED - RTM	REVISED -	
	DRAWN - JRR	REVISED -	
PLOT SCALE = @SCALE@	CHECKED - RTM	REVISED -	
PLOT DATE = @DATE@	DATE - 10/22/12	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO 5 OF 6 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3512	02-00177-00 WR	COOK	142	15
PROJECT NO. M-8003(426)		CONTRACT NO. 63514		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		